BUILDING 8700 - TARGET BUILDING - ROOM FINISH SCHEDULE

ROOM #	ROOM NAME	FLOOR	BASE	WAINSCOT	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING HEIGHT	CEILING TYPE	REMARKS
TA-B001	TANK PIT BELOW	304 L S.S.	304 L S.S.	–	304 L S.S.	304 L S.S.	304 L S.S.	304 L S.S.	11'-2	HPC-4	
TA-B002	TANK PIT BELOW	304 L S.S.	304 L S.S.	–	304 L S.S.	304 L S.S.	304 L S.S.	304 L S.S.	12'-0"	HPC-4	
TA-B003	TANK PIT BELOW	304 L S.S.	304 L S.S.	–	304 L S.S.	304 L S.S.	304 L S.S.	304 L S.S.	13'-0"	HPC-4	
TA-B004	TANK PIT BELOW	304 L S.S.	304 L S.S.	–	304 L S.S.	304 L S.S.	304 L S.S.	304 L S.S.	10'-0"	HPC-4	
TA-B101	LABYRINTH	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	14'-0"	PAINT	
TA-B102	SYSTEM #2 COOLING LOOP	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	14'-0"	HPC-4	
TA-B103	SYSTEM #1 COOLING LOOP	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	14'-0"	HPC-4	
TA-B104	D.I. WATER	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B105	D1 / POLISHED WATER	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B106	LAB	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B107	STAIR NO.1	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-B108	JANITORS CLOSET	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B109	CORRIDOR	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B110	COMMUNICATIONS ROOM	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-1	
TA-B111	FORK LIFT CHARGE & REPAIR	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B112	CONTROL ROOM	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-1	
TA-B113	CORRIDOR	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B114	WOMENS LOCKER ROOM	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-B115	WOMEN'S SHOWERS	HPC-5	HPC-5	–	HPC-5	HPC-5	HPC-5	HPC-5	9'-0"	HPC-5	PROVIDE HPC-5 IN SHOWER STALLS
TA-B116	WOMEN'S TOILETS	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-B117	MEN'S TOILETS	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-B118	MEN'S LOCKER ROOM	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-B119	MEN'S SHOWERS	HPC-5	HPC-5	–	HPC-5	HPC-5	HPC-5	HPC-5	9'-0"	HPC-5	PROVIDE HPC-5 IN SHOWER STALLS
TA-B120	HOT CELL BOTTOM LOADING & TRANS.	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	VARIES	HPC-4	
TA-B121	STAIR NO.3	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	VARIES	HPC-4	
TA-B122	AIR LOCKS (5)	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	VARIES	HPC-5	
TA-B123	STAIR NO.2	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-B124	PERSON DECON	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B125	H.P. OFFICE	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-1	
TA-B126	CORRIDOR	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B127	ELEVATOR MACHINE ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	12'-6"	EXPOSED	
TA-B128	STAIR NO.5	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-B129	HYDRAULIC PUMP ROOM	SEALED CONC.	–		PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B130	JANITORS CLOSET	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B131	STAIR NO.4	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-B132	AIR LOCKS	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	VARIES	PAINT	
TA-B133	LIQUID WASTE PROCESSING	304 L S.S.	304 L S.S.	–	PAINT	PAINT	PAINT	PAINT	16'-8"	EXPOSED	
TA-B134	STORAGE ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B135	TRUCK BAY	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B136	FIRE PROTECTION RISER ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B137	CORRIDOR	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B138	LLLW TANKS (Hg)	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	16'-8"	HPC-4	
TA-B139	PUMP VALVE, & IX VAULT	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	10'-0"	HPC-4	
TA-B140	DECAY / RCRA ROOM	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	HPC-2	PAINT	
TA-B141	CORRIDOR	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B142	CORRIDOR	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B143	MECH/ ELEC ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B144	CORRIDOR	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B145	STAIR NO.6	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-B147	SECONDARY CONFINEMENT EXHAUST	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	PAINT	
TA-B148	PRIMARY CONFINEMENT EXHAUST	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	PAINT	
TA-B149	MERCURY REMOVAL	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	VARIES	HPC-4	
TA-B150	CARBON FILTER ROOM	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	16'-8"	HPC-4	
TA-B152	CORRIDOR	304 L S.S./HPC-1	12" S.S./HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	14'-0"	HPC-4	
TA-B153	SYSTEM #4 COOLING LOOP	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	14'-0"	HPC-4	
TA-B154	SYSTEM #3 COOLING LOOP	304 L S.S.	12" 304 L S.S.	–	HPC-4	HPC-4	HPC-4	HPC-4	14'-0"	HPC-4	
TA-B155	AIR LOCK	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	VARIES	PAINT	
TA-B156	TRITIUM REMOVAL	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	18'-6"	PAINT	
TA-B157	SANITARY SEWER ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	18'-6"	EXPOSED	
TA-B158	UTILITY TUNNEL	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	12'-0"	PAINT	
TA-B159	STAIR NO.7	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-B201	LLLW SAMPLING ROOM	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	–	PAINT	
TA-100	STAIR NO.8	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-101	INSTRUMENT PIT	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-102	INSTRUMENT AREA	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-103	TELECOMMUNICATIONS ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-104	STAIR NO.1	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-105	BREAK ROOM	VCT	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-106	H.P. OFFICE	VCT	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-107	LOBBY	VCT	4" RUBBER		PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-108	LAB AND WORK AREA	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-109	TRUCK BAY	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-110	RTBT TUNNEL	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	–	HPC-4	
TA-111	TARGET MONOLITH	–	–	–	–	–	–	–	–	–	
TA-112	SERVICE GALLERY	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	28'-0"	HPC-4	
TA-113	INSTRUMENT DECONTAMINATION AREA	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4		HPC-4	
TA-114	HOT CELL	*	*	*	*	*	*	*	*	*	* PER "J" SERIES DRAWINGS
TA-115	MANIPULATOR GALLERY	HPC-1	HPC-1	–	HPC-4	HPC-4	HPC-4	HPC-4	–	HPC-4	
TA-116	STAIR NO.2	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-117	AIR LOCK	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	–	PAINT	
TA-118	MOCK UP TEST STAND AREA	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-119	AIR PALLET ZONE	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-120	STAIR NO.5	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-121	FORK LIFT CHARGE & REPAIR	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-122	STAIR NO.7	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-123	INSTRUMENT AREA	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-124	LAB AND WORK AREA	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-125	TRUCK BAY	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-126	STAIR NO.6	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-128	SWITCH GEAR	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	9'-0"	EXPOSED	
TA-129	WOMENS WASHROOM	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-130	MENS WASHROOM	SEALED CONC.	4" RUBBER	–	PAINT	PAINT	PAINT	PAINT	9'-0"	ACT-3	
TA-131	2TU BEAM LINE ENCLOSURE	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-132	2TU INSTRUMENT ENCLOSURE	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-133	11TU INSTRUMENT ENCLOSURE	HPC-2	HPC-2	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	

BUILDING 8700 - TARGET BUILDING - ROOM FINISH SCHEDULE

ROOM #	ROOM NAME	FLOOR	BASE	WAINSCOT	WALLS NORTH	WALLS EAST	WALLS SOUTH	WALLS WEST	CEILING HEIGHT	CEILING TYPE	REMARKS
TA-201	STAIR NO.8	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-202	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-203	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-204	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-205	STAIR NO.1	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-206	OVERLOOK	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-207	STAIR NO.7	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-208	CORRIDOR	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	8'-0"	EXPOSED	
TA-210	MAGNET ACCESS	HPC-1	HPC-1	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-211	TARGET MONOLITH	–	–	–	–	–	–	–	–	–	
TA-212	DELAY TANK CAVITY	304 L S.S.	–	–	304 L S.S.	304 L S.S.	304 L S.S.	304 L S.S.	VARIES	304 L S.S.	
TA-213	GAS LIQUID SEPARATOR CAVITY	304 L S.S.	–	–	304 L S.S.	304 L S.S.	304 L S.S.	304 L S.S.	VARIES	304 L S.S.	
TA-214	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-215	STAIR NO.2	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-216	STAIR NO.5	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-217	OVERLOOK	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-218	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-219	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-220	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-221	STAIR NO.6	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	VARIES	EXPOSED	
TA-222	OVERLOOK	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-300	STAIR NO.7	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-302	SHINE SHIELD AREA	HPC-1	HPC-1	–	HPC-1	HPC-1	HPC-1	HPC-1	–	EXPOSED	
TA-303	HIGH BAY	HPC-1	HPC-1	–	HPC-1	HPC-1	HPC-1	HPC-1	–	EXPOSED	
TA-304	AIR LOCK	HPC-1	HPC-1	–	HPC-1	HPC-1	HPC-1	HPC-1	–	EXPOSED	
TA-305	STAIR NO.2	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-306	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-307	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-308	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-309	STAIR NO.5	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-310	OVERLOOK	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-401	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-402	MECHANICAL EQUIPMENT	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-403	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-404	MECHANICAL EQUIPMENT	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-405	STAIR NO.5	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-406	OVER LOOK	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-407	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-408	MECHANICAL EQUIPMENT	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-409	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-410	MECHANICAL EQUIPMENT	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-411	HYDROGEN UTILITY ROOM	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	GYP. BD.	
TA-412	WALKWAY	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-413	HYDROGEN MAINTENANCE AREA	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-414	STAIR NO.7	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-501	ROOF ACCESS	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	
TA-501	ROOF ACCESS	SEALED CONC.	–	–	PAINT	PAINT	PAINT	PAINT	–	EXPOSED	

NO REPRESENTATION OR WARRANTY, EXPRESSED OR IMPLIED, IS MADE AS TO THE ACCURACY, COMPLETENESS OR USEFULNESS OF THE INFORMATION OR STATEMENTS CONTAINED IN THESE DRAWINGS, OR THAT THE USE OR DISCLOSURE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THESE DRAWINGS MAY NOT INFRINGE PRIVATE RIGHTS OF OTHERS. NO LIABILITY IS ASSUMED WITH RESPECT TO THE USE OF, OR FOR DAMAGES RESULTING FROM THE USE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THESE DRAWINGS. DRAWINGS MADE AVAILABLE FOR INFORMATION TO BIDDER ARE NOT TO BE USED FOR OTHER PURPOSES AND ARE TO BE RETURNED UPON REQUEST OF THE FORWARDING CONTRACTOR.

NUMBER OF SECTION OR DETAIL
DRAWING ON WHICH SECTION OR DETAIL IS SHOWN OR TAKEN
SECTION AND DETAIL KEY

THIS DOCUMENT CONTROLLED BY
CHANGE CONTROL SYSTEM 3
ENGINEERING PROCEDURE SNS-ENG-G001

REV	CHANGE TYPE	CHANGE CONTROL SYSTEM	CHANGE REQUEST NUMBER	DESCRIPTION	DSN	CHK	DEPT
0				CERTIFIED FOR CONSTRUCTION – 10/26/01	MBB	ED	

REVISION OR ISSUE PURPOSE

DATE	PE	DATE	PJ	DATE	REQ	DATE	UTB	DATE	RPE	RPE NO	DATE
	RDB	11/13/01	RAD	11/13/01				11/13/01	RLB	102104	10/26/01

REVISION APPROVALS

REW	–	WRS	AK	WRS	BWJ	–	MP	–	ED
ST	CV	EC	EE	EM	IE	M	PD	SE	AR

SQUAD CHECK

RPE
ROBERT L. BARNES REGISTERED ARCHITECT TENNESSEE 102104 STATE OF TENNESSEE
26 OCT '01
REV. DATE

DSN	M. BRADLEY	10/26/01
DRW	M. SICILIA	10/26/01
CHK	E.DENSON	10/26/01
DEPT		
PE	B.J. Davern	11/13/01
PJ	R.A. Dean	11/13/01
REQ		
UTB	M. Hawkins	11/13/01

DRAWING APPROVALS

108030700-A8E-8000-A002

Knight/Jacobs Joint Venture
701 Scarboro Road, MS 8253
Oak Ridge, TN 37830
865-241-9433
fax 865-241-3400

KNIGHT
Knight Advanced Technology
549 West Randolph Street
Chicago, IL 60661

UT-BATTELLE
Oak Ridge National Laboratory
managed for the DEPARTMENT OF ENERGY under U.S. GOVERNMENT contract DE-AC05-00OR22725
UT-BATTELLE, LLC. • Oak Ridge, Tennessee

PROJECT NAME:
SPALLATION NEUTRON SOURCE

TARGET, 2TU, 11TU, & COMPRESSOR BUILDING ROOM SCHEDULES

1	48	49	50	PLANT	BLDG	FL	SH.	OF	TYPE	CLASS
3	A	X	X	8	8000		1	1		U

51	52	53	WBS		REV
NC	NA		1.8.3.7	A7.10.30	0

AutoCAD

Date: 10/26/2001 Time: 14:53:20
Username: DSCHMIT
C:\ACAD2000\DATA\WWW_TEMP_DATA\DWG_SAFING_FLOFTLAT-10-30.DWG