


**SLOPED CONTROLS**

**A**



**VERTICAL CONTROLS**

**B**

- A. MOUNT THERMOSTATIC CONTROLS AND/OR SWITCHES IN PANEL AS RECOMMENDED BY MFR. WHERE APPLICABLE CONTROL PLATES SHALL BE SECURED WITH S/S COUNTERSUNK SHEET METAL SCREWS.
- B. PILOT LIGHTS SHALL BE MOUNTED ABOVE OR BELOW CONTROL OR SWITCH TO PROVIDE THE MOST READILY VISIBLE POSITION. PILOT LIGHTS MOUNTED TO THE SIDES IN A SERIES OF CONTROLS OR SWITCHES WILL NOT BE ACCEPTABLE.
- C. KNOBS, TOGGLES AND GUARDS SHALL NOT PROTRUDE BEYOND THE FIXTURE TOP EDGE; IT SHALL BE THE RESPONSIBILITY OF THE EQUIPMENT CONTRACTOR TO ADJUST THE DEPTH OF THE PANEL RECESS TO COMPLY WITH THIS REQUIREMENT.
- D. LENGTH OF RECESS SHALL ACCOMODATE REQUIRED SERIES OF CONTROLS AS SPECIFIED WHILE MAINTAINING ADEQUATE SPACING AROUND EACH CONTROL.
- E. ENCLOSE CONTROLS IN 22 GA. (.8MM) STEEL BOX. IF ENCLOSURE IS NOT PROVIDED OTHERWISE.

APPROVED: 08-01-01