LEVEL 3

| ROOM # | ROOM NAME | FLOOR | BASE | WALLS NORTH | EAST | SOUTH | WEST | CEILING HEIGHT | CEILING TYPE | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|
| CL-3-1-1 | STAIR NO. 2 | RUBBER | RUBBER | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | VARIES | METAL, PAINT | PAINT STAIR; SEE NOTE 1 |
| CL-3-1-2 | ELEVATOR LOBBY | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | SEE ELEVATION 1, DRAWING A5.10.43 |
| CL-3-1-3 | TELEPHONE | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-1-4 | ELECTRICAL | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-1-5 | CORRIDOR | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 10'-6" | ACT 1 | |
| CL-3-1-6 | WOMEN'S TOILET | CT | CT | GWB, PAINT | CT | GWB, PAINT | GWB, PAINT | 9'-5" | GWB, PAINT | |
| CL-3-1-7 | MEN'S TOILET | CT | CT | GWB, PAINT | GWB, PAINT | GWB, PAINT | CT | 9'-5" | GWB, PAINT | |
| CL-3-1-8 | COFFEE | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 8'-0" | ACT 1 | SEE ELEVATION 5, DRAWING A5.10.44 |
| CL-3-1-9 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-10 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-11 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-12 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-13 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-14 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-15 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-16 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-17 | COPY | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 8'-0" | ACT 1 | SEE ELEVATION 6, DRAWING A5.10.44 |
| CL-3-1-18 | CORRIDOR | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-19 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-20 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-21 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-22 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-1-23 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-1-24 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-1-25 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-1-26 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| ROOM # | ROOM NAME | FLOOR | BASE | WALLS NORTH | EAST | SOUTH | WEST | CEILING HEIGHT | CEILING TYPE | REMARKS |
| CL-3-2-27 | CONFERENCE | CARPET | RESIL. | GWB, PAINT | MARKER SURF. | GWB, PAINT | MARKER SURF. | 9'-5" | ACT 1 | SEE ELEVATION 2, DRAWING A5.10.42 |
| CL-3-2-28 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-29 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-30 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-31 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-32 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-33 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-34 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-35 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-36 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-37 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-38 | CORRIDOR | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-39 | DOCUMENT CONTROL | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-40 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-41 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-42 | JANITOR/STORAGE | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-2-43 | ELEVATOR LOBBY | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | SEE ELEVATION 3, DRAWING A5.10.43 |
| CL-3-2-44 | RECEPTION | CARPET | RESIL. | OPEN | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-45 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-46 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-47 | COPY/STORAGE | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 8'-0" | ACT 1 | SEE ELEVATION 9, DRAWING A5.10.44 |
| CL-3-2-48 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-49 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-50 | TELEPHONE | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-2-51 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-52 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-53 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-54 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-55 | OPEN OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-56 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-57 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-58 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-59 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-60 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-61 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-62 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-63 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-64 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-65 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-66 | ELECTRICAL | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-2-67 | STAIR NO. 1 | RUBBER | RUBBER | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | VARIES | METAL, PAINT | PAINT STAIR; SEE NOTE 1 |
| CL-3-2-68 | MEN'S TOILET | CT | CT | GWB, PAINT | GWB, PAINT | GWB, PAINT | CT | 9'-5" | GWB, PAINT | |
| CL-3-2-69 | WOMEN'S TOILET | CT | CT | GWB, PAINT | CT | GWB, PAINT | GWB, PAINT | 9'-5" | GWB, PAINT | |
| CL-3-2-70 | COFFEE | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 8'-0" | ACT 1 | SEE ELEVATION 2, DRAWING A5.10.44 |
| CL-3-2-71 | CORRIDOR | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-72 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-73 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-74 | OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-2-75 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-2-76 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-2-77 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-2-78 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| ROOM # | ROOM NAME | FLOOR | BASE | WALLS NORTH | EAST | SOUTH | WEST | CEILING HEIGHT | CEILING TYPE | REMARKS |
| CL-3-3-79 | STAIR NO. 3 | RUBBER | RUBBER | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | VARIES | METAL, PAINT | PAINT STAIR; SEE NOTE 1 |
| CL-3-3-80 | OPEN OFFICE | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A |
| CL-3-3-81 | CORRIDOR | CARPET | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A |
| CL-3-3-82 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-83 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-84 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-85 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-86 | CORRIDOR | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | SEE NOTE 1 |
| CL-3-3-87 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-88 | STORAGE | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-89 | TELEPHONE | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-90 | ELECTRICAL | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-91 | MECHANICAL ROOM | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-92 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-93 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-94 | CORRIDOR | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A |
| CL-3-3-95 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-96 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-97 | CORRIDOR | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A |
| CL-3-3-98 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-99 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-100 | CORRIDOR | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A |
| CL-3-3-101 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-102 | DRY LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-103 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-104 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-105 | CORRIDOR | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A |
| CL-3-3-106 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-107 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-108 | ELECTRICAL | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-109 | TELEPHONE | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-110 | VESTIBULE | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-3-111 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-112 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-113 | CORRIDOR | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | |
| CL-3-3-114 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-115 | WET LAB | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | PROVIDED PER ALTERNATE #1A, SEE NOTE 1 |
| CL-3-3-116 | MECHANICAL ROOM | SEALED | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | TO STRUCTURE | EXPOSED | SEE NOTE 1 |
| CL-3-3-117 | STAIR NO. 4 | RUBBER | RUBBER | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | VARIES | METAL, PAINT | PAINT STAIR; SEE NOTE 1 |
| CL-3-3-118 | COFFEE | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A<br>SEE ELEVATION 8, DRAWING A5.10.44 |
| CL-3-3-119 | COPY | VCT | RESIL. | GWB, PAINT | GWB, PAINT | GWB, PAINT | GWB, PAINT | 9'-5" | ACT 1 | PROVIDED PER ALTERNATE #1A<br>SEE ELEVATION 11, DRAWING A5.10.44 |
| CL-3-3-120 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-3-121 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |
| CL-3-3-122 | NOT USED | -- | -- | -- | -- | -- | -- | -- | -- | |

NOTES:
1. PAINTED WALLS TO UNDERSIDE OF STRUCTURAL DECK, PAINTED DECK AND PAINTED FIREPROOFING. UTILITIES NOT PAINTED UNLESS INDICATED BY MECHANICAL, ELECTRICAL, OR PLUMBING SPECIFICATIONS

NO REPRESENTATION OR WARRANTY, EXPRESSED OR IMPLIED, IS MADE AS TO THE ACCURACY, COMPLETENESS OR USEFULNESS OF THE INFORMATION OR STATEMENTS CONTAINED IN THESE DRAWINGS, OR THAT THE USE OR DISCLOSURE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THESE DRAWINGS MAY NOT INFRINGE PRIVATE RIGHTS OF OTHERS. NO LIABILITY IS ASSUMED WITH RESPECT TO THE USE OF, OR FOR DAMAGES RESULTING FROM THE USE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THESE DRAWINGS. DRAWINGS MADE AVAILABLE FOR INFORMATION TO BIDDER ARE NOT TO BE USED FOR OTHER PURPOSES AND ARE TO BE RETURNED UPON REQUEST OF THE FORWARDING CONTRACTOR.

NUMBER OF SECTION OR DETAIL
DRAWING ON WHICH SECTION OR DETAIL IS SHOWN OR TAKEN
SECTION AND DETAIL KEY

THIS DOCUMENT CONTROLLED BY
CHANGE CONTROL SYSTEM 4
ENGINEERING PROCEDURE SNS-ENG-G001

| REV | CHANGE TYPE | CHANGE CONTROL SYSTEM | CHANGE CONTROL NUMBER | DESCRIPTION | DSN | CHK | DEPT |
|---|---|---|---|---|---|---|---|
| 1 | | | | CERTIFIED FOR CONSTRUCTION – 12/20/01 | CF | ED | |
| 0 | – | – | – | CERTIFIED FOR CONSTRUCTION – MAY 15, 2001 | CF | ED | |

REVISION OR ISSUE PURPOSE

| DATE | PE | DATE | PJ | DATE | REQ | DATE | UTB | DATE | RPE | RPE NO | DATE |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | RLB 12/1/01 | | RLB 12/1/01 | | | | RLB 12/20/01 | RLB | 102104 | 12/20/01 | |
| | CLG 9/6/01 | | JS 8/21/01 | | | | JRL 9/25/01 | RLB | 102104 | 5/15/01 | |

REVISION APPROVALS

| ST | CV | EC | EE | EM | IE | M | PD | SE | AR |
|---|---|---|---|---|---|---|---|---|---|
| RW | AW | BWJ | PD | BWJ | BWJ | -- | BWJ | -- | ED |
| SC | AW | WRS | RL | WRS | BWJ | -- | WRS | -- | WAS |

SQUAD CHECK

RPE
ROBERT L. BASINES REGISTERED ARCHITECT NO. 102104 STATE OF TENNESSEE
12/12/01

| REV. | DATE |
|---|---|
| | |

DRAWING APPROVALS

| | | |
|---|---|---|
| DSN | H. BAUMAN | 5/15/01 |
| DRW | A. OWENS | 5/15/01 |
| CHK | E. DENSON | 5/15/01 |
| DEPT | | |
| PE | C.L. GARREN | 9/6/01 |
| PJ | J. STELLERN | 8/21/01 |
| REQ | | |
| UTB | J.R. LAWSON | 9/25/01 |

108031400-A8E-8600-A170

Knight Jacobs
KnightJacobs Joint Venture
701 Scarboro Road, MS 8253
Oak Ridge, TN 37830
865-241-9433
fax 865-241-3400

KNIGHT
Knight Advanced Technology
540 West Randolph Street
Chicago, IL 60661

UT-BATTELLE
Oak Ridge National Laboratory
managed for the DEPARTMENT OF ENERGY under
U.S. GOVERNMENT contract DE-AC05-00OR22725
UT-BATTELLE, LLC. © Oak Ridge, Tennessee

PROJECT NAME:
SPALLATION NEUTRON SOURCE
CENTRAL LAB AND OFFICE BUILDING
ROOM FINISH SCHEDULE
SHEET 3 OF 4

| 1 | 48 | 49 | 50 | PLANT | BLDG | FL | SH. | OF | TYPE | CLASS |
|---|---|---|---|---|---|---|---|---|---|---|
| 3 | A | X | X | 8 | 8600 | | 1 | 1 | G | U |

| 51 | 52 | 53 | | | |
|---|---|---|---|---|---|
| NC | NA | | WBS 1.8.3.14 | A7.10.42 | REV 1 |

Date: 12/17/2001 Time: 20:30:02
Username: DSGUNNS
CH:\P_WBJOPROJECTS\7600\700_CADD\W0A_SB\140_PLOT\A7-10-42.DWG