DOOR #	ROOM NAME	TYPE	THICK	WIDTH	HEIGHT	MAT'L	GLASS	FIRE RATING	FRAME #	HEAD	JAMBS	THRESHOLD	HARDWARE GROUP	REMARKS
	DOOR (DBL. LETTER INDICATES PAIR)									DOOR DETAILS				
CL-2-3-81	STAIR NO. 3	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		5	
CL-2-3-82A	VACUUM LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-2-3-82B	VACUUM LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-83A	HIGH POWER LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-83B	HIGH POWER LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-84A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-2-3-84B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-2-3-85A	PHYSICS STAFF LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-85B	PHYSICS STAFF LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-86	STORAGE	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-2-3-87	TELEPHONE	F	1-3/4"	3'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-2-3-88	ELECTRICAL	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-2-3-89A	OPERATIONS STAFF LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-2-3-89B	OPERATIONS STAFF LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-90	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-91	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-92	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-93A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1D
CL-2-3-93B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1D
CL-2-3-94	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-95	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-96	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-97	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-98	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-99	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-100	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-101	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-102A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1D
CL-2-3-102B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1D
CL-2-3-103	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-104	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-105	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-106	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-107	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-108	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-109	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-110	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-111	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-112	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-113	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-114A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1D
CL-2-3-114B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1D
CL-2-3-115	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-116	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-117	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-118	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-119	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-120	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-2-3-121	VESTIBULE	FF	1-3/4"	6'-0"	9'-2"	HM			FR-1A	1-A9.10.40	1-A9.10.40		17	
CL-2-3-122	TELEPHONE CLOSET	F	1-3/4"	3'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-2-3-123	ELECTRICAL CLOSET	F	1-3/4"	3'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-2-3-124	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-125	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-126A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-2-3-126B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-2-3-127	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-128	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-129	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1D
CL-2-3-130	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4"TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-2-3-131	STAIR NO. 4	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		5	
CL-2-3-132	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-133	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-134	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-3-135	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	

DOOR #	ROOM NAME	TYPE	THICK	WIDTH	HEIGHT	MAT'L	GLASS	FIRE RATING	FRAME #	HEAD	JAMBS	THRESHOLD	HARDWARE GROUP	REMARKS
	DOOR (DBL. LETTER INDICATES PAIR)									DOOR DETAILS				
CL-2-4-136	CONTROL ROOM OBSER.	FF	1-3/4"	6'-0"	6'-10"	WOOD		1-1/2 HR.	FR-1A	1-A9.10.40	6-A9.10.40		22A	ACCESS CONTROL
CL-2-4-137	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-138	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-139	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-4-140	TELEPHONE CLOSET	F	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-2-4-141	ELECTRICAL CLOSET	F	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-2-4-142A	OFFICE	F	1-3/4"	3'-0"	6'-10"	WOOD		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		10	
CL-2-4-142B	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-143	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-144	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-145	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-146	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-2-4-147	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-4-148	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-2-5-1A	PEDESTRIAN BRIDGE	FF	1-3/4"	7'-0"	7'-1"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	6-A9.10.40		9	PROVIDED PER ALTERNATE #2
CL-2-5-1B	PEDESTRIAN BRIDGE	FF	1-3/4"	7'-0"	7'-1"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	6-A9.10.40		26	PROVIDED PER ALTERNATE #2

LEVEL 3

DOOR #	ROOM NAME	TYPE	THICK	WIDTH	HEIGHT	MAT'L	GLASS	FIRE RATING	FRAME #	HEAD	JAMBS	THRESHOLD	HARDWARE GROUP	REMARKS
	DOOR (DBL. LETTER INDICATES PAIR)									DOOR DETAILS				
CL-3-1-1	STAIR NO. 2	F	1-3/4"	3'-0"	6'-10"	WOOD		1-1/2 HR.	FR-1B	4-A9.10.40	4-A9.10.40		23	
CL-3-1-2	ELEVATOR LOBBY	FF	1-3/4"	6'-0"	6'-10"	WOOD		3/4 HR.	FR-1A	1-A9.10.40	6-A9.10.40		9	
CL-3-1-3	TELEPHONE	F	1-3/4"	3'-0"	6'-10"	WOOD		3/4 HR.	FR-1A	1-A9.10.40	1-A9.10.40		4B	UNDERCUT DOOR 3/4"
CL-3-1-4	ELECTRICAL	F	1-3/4"	3'-0"	6'-10"	WOOD		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-3-1-5	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-1-6	WOMEN'S TOILET	L	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		8	
CL-3-1-7	MEN'S TOILET	L	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		8	
CL-3-1-8	COFFEE	F	1-3/4"	3'-0"	6'-10"	WOOD		3/4 HR.	FR-1A	1-A9.10.40	1-A9.10.40		5A	
CL-3-1-9	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-10	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-11	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-12	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-13	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-14	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-15	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-16	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-17	COPY	F	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		5A	
CL-3-1-18	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-1-19	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-20	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-21	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-22	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-1-23	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-1-24	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-1-25	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-1-26	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	

DOOR #	ROOM NAME	TYPE	THICK	WIDTH	HEIGHT	MAT'L	GLASS	FIRE RATING	FRAME #	HEAD	JAMBS	THRESHOLD	HARDWARE GROUP	REMARKS
	DOOR (DBL. LETTER INDICATES PAIR)									DOOR DETAILS				
CL-3-2-27A	CONFERENCE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		5A	
CL-3-2-27B	CONFERENCE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4"TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		5A	
CL-3-2-28	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-29	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-30	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-31	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-32	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-33	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-34	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-35	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-36	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-37	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-38	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-2-39 A	DOCUMENT CONTROL	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10A	
CL-3-2-39 B	DOCUMENT CONTROL	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10A	
CL-3-2-40	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-41	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-42	JANITOR/STORAGE	L	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		4	
CL-3-2-43	ELEVATOR LOBBY	FF	1-3/4"	6'-6"	6'-0"	WOOD		3/4 HR.	FR-1A	1-A9.10.40	1-A9.10.40		9	
CL-3-2-44	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-2-45	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-46	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-47	COPY/STORAGE	F	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		5A	
CL-3-2-48	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-49	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-50	TELEPHONE	F	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		4B	UNDERCUT DOOR 3/4"
CL-3-2-51	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-52	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-53	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-54	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-55	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-2-56	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-57	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-58	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-59	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-60	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-61	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-62	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-63	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-64	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-65	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP		FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-66	ELECTRICAL	F	1-3/4"	3'-0"	6'-10"	WOOD		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-3-2-67	STAIR NO. 1	F	1-3/4"	3'-0"	6'-10"	WOOD		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		10	
CL-3-2-68	MEN'S TOILET	L	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		8	
CL-3-2-69	WOMEN'S TOILET	L	1-3/4"	3'-0"	6'-10"	WOOD			FR-1A	1-A9.10.40	1-A9.10.40		8	
CL-3-2-70	COFFEE	F	1-3/4"	3'-0"	6'-10"	WOOD		3/4 HR.	FR-1A	1-A9.10.40	1-A9.10.40		5A	
CL-3-2-71	CORRIDOR	TT	1-3/4"	6'-0"	6'-10"	HM	1/4" TEMP	3/4 HR.	FR-1A	3-A9.10.40	6-A9.10.40		9	GLASS TRANSOM TO 9'-4"
CL-3-2-72	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-73	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-74	OFFICE	C	1-3/4"	3'-0"	6'-10"	WOOD	1/4" TEMP	3/4 HR.	FR-1A	1-A9.10.40	1,3-A9.10.40		10	
CL-3-2-75	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-2-76	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-2-77	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-2-78	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	

DOOR #	ROOM NAME	TYPE	THICK	WIDTH	HEIGHT	MAT'L	GLASS	FIRE RATING	FRAME #	HEAD	JAMBS	THRESHOLD	HARDWARE GROUP	REMARKS
	DOOR (DBL. LETTER INDICATES PAIR)									DOOR DETAILS				
CL-3-3-79	STAIR NO. 3	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		5	
CL-3-3-80	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-81	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-82	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-3-3-83	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-84	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-85	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-86A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-3-3-86B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-3-3-87	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-3-3-88	STORAGE	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-89	TELEPHONE	F	1-3/4"	3'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-3-3-90	ELECTRICAL	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-3-3-91A	MECHANICAL ROOM	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-91B	MECHANICAL ROOM	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-91C	MECHANICAL ROOM	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-91D	MECHANICAL ROOM	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-91E	MECHANICAL ROOM	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-92	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-93	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-94	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1A
CL-3-3-95	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-96	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-97	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-98	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-99	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-100	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1A
CL-3-3-101	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-102	DRY LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-103	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-104	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-105	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	PROVIDED PER ALTERNATE #1A
CL-3-3-106	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-107	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-108	ELECTRICAL	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-3-3-109	TELEPHONE	F	1-3/4"	3'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		4	UNDERCUT DOOR 3/4"
CL-3-3-110	VESTIBULE	FF	1-3/4"	6'-0"	9'-2"	HM			FR-1A	1-A9.10.40	1-A9.10.40		17	
CL-3-3-111	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-3-3-112	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-113A	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-3-3-113B	CORRIDOR	FF	1-3/4"	6'-4"	6'-10"	HM			FR-1A	1-A9.10.40	8-A9.10.40		9	
CL-3-3-114	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	PROVIDED PER ALTERNATE #1A
CL-3-3-115	WET LAB	BB	1-3/4"	5'-0"	6'-10"	HM	1/4" TEMP		FR-1A	1-A9.10.40	1-A9.10.40		14	
CL-3-3-116	MECHANICAL ROOM/STORAGE	FF	1-3/4"	6'-0"	6'-10"	HM			FR-1A	1-A9.10.40	1-A9.10.40		2	
CL-3-3-117	STAIR NO. 4	F	1-3/4"	3'-0"	6'-10"	HM		1-1/2 HR.	FR-1A	1-A9.10.40	1-A9.10.40		5	
CL-3-3-118	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-119	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-120	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-121	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	
CL-3-3-122	NOT USED	--	--	--	--	--	--	--	--	--	--	--	--	

NO REPRESENTATION OR WARRANTY, EXPRESSED OR IMPLIED, IS MADE AS TO THE ACCURACY, COMPLETENESS OR USEFULNESS OF THE INFORMATION OR STATEMENTS CONTAINED IN THESE DRAWINGS, OR THAT THE USE OR DISCLOSURE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THESE DRAWINGS MAY NOT INFRINGE PRIVATE RIGHTS OF OTHERS. NO LIABILITY IS ASSUMED WITH RESPECT TO THE USE OF, OR FOR DAMAGES RESULTING FROM THE USE OF ANY INFORMATION, APPARATUS, METHOD, OR PROCESS DISCLOSED IN THESE DRAWINGS. DRAWINGS MADE AVAILABLE FOR INFORMATION TO BIDDER ARE NOT TO BE USED FOR OTHER PURPOSES AND ARE TO BE RETURNED UPON REQUEST OF THE FORWARDING CONTRACTOR.

SECTION AND DETAIL KEY: NUMBER OF SECTION OR DETAIL / DRAWING ON WHICH SECTION OR DETAIL IS SHOWN OR TAKEN

THIS DOCUMENT CONTROLLED BY
CHANGE CONTROL SYSTEM 4
ENGINEERING PROCEDURE SNS-ENG-G001

REV	CHANGE TYPE	CHANGE CONTROL SYSTEM	CHANGE REQUEST NUMBER	DESCRIPTION	DSN	CHK	DEPT	DATE	PE	DATE	PJ	DATE	REQ	DATE	UTB	DATE	RPE	RPE NO	DATE	ST	CV	EC	EE	EM	IE	M	PD	SE	AR
1				CERTIFIED FOR CONSTRUCTION - 12/20/01	CF	ED				12/01		12/01				12/26/01	RLB	102104	12/20/01	RW	AW	BWJ	PD	BWJ	BWJ	--	BWJ	--	ED
0	-	-	-	CERTIFIED FOR CONSTRUCTION - MAY 15, 2001	CF	ED			CLG	9/6/01	JS	8/21/01			JRL	9/25/01	RLB	102104	5/15/01	SC	AW	WRS	RL	WRS	BWJ	--	WRS	--	WAS

REVISION OR ISSUE PURPOSE — REVISION APPROVALS — SQUAD CHECK

RPE			
	DSN	H. BAUMAN	5/15/01
	DRW	A. OWENS	5/15/01
	CHK	E. DENSON	5/15/01
	DEPT		
	PE	C.L. GARREN	9/6/01
	PJ	J. STELLERN	8/21/01
	REQ		
REV. DATE	UTB	J.R. LAWSON	9/25/01

DRAWING APPROVALS

ROBERT L. BARNES REGISTERED ARCHITECT NO. 102104 STATE OF TENNESSEE

108031400-A8E-8600-A173

Knight/Jacobs Joint Venture
701 Scarboro Road, MS 8253
Oak Ridge, TN 37830
865-241-9433
fax 865-241-3400

KNIGHT
Knight Advanced Technology
549 West Randolph Street
Chicago, IL 60661

UT-BATTELLE
Oak Ridge National Laboratory
managed for the DEPARTMENT OF ENERGY under
U.S. GOVERNMENT contract DE-AC05-00OR22725
UT-BATTELLE, LLC, Oak Ridge, Tennessee

PROJECT NAME:

SPALLATION NEUTRON SOURCE

CENTRAL LAB AND OFFICE BUILDING
DOOR SCHEDULE
SHEET 3 OF 4

1	48	49	50	PLANT	BLDG	FL	SH.	OF	TYPE	CLASS
3	A	X	X	8	8600		1	1	G	U
51	52		53		WBS					REV
NC	NA				1.8.3.14	A7.30.42				1

AutoCAD

NEXT ASS'Y: FINAL ASS'Y:

Date: 12/17/2001 Time: 20:29:34
Username: SICILIANS
CHI-F_VOL2:PROJECTS\7000\700_CADD\TASK_2B\740_PLOT\A7-30-42.DWG