

SEQUENCE OF OPERATION

GENERAL: THE SYSTEM SHALL CONSIST OF AN AIR HANDLING UNIT WITH SENSIBLE CHILLED WATER COOLING COILS. THE SYSTEM SHALL HAVE ELECTRONICALLY OPERATED VALVES AND ITS OWN DDC STAND ALONE LOCAL CONTROL STATION (LCS). ALL SETPOINTS SHALL BE ADJUSTABLE.

TOLERANCES AND SETPOINTS: SPACE COOLING TOLERANCE: 67 - 69F SPACE COOLING SETPOINT: 68F SUPPLY AIR SETPOINT: 68F

SYSTEM START/STOP CONTROL: THE UNITS SHALL BE STARTED AND STOPPED VIA THE BUILDING DDC CENTRAL CONTROL OR THE LOCAL CONTROL STATION (LCS). WHEN A FAN SYSTEM IS STARTED, THE FOLLOWING EVENTS SHALL OCCUR: 1. ITS RESPECTIVE CONTROL SYSTEM SHALL BE ENABLED. 2. THE SUPPLY AIR FAN SHALL START. 3. CONFIRMATION OF AIR FLOW SHALL BE BY AIR FLOW MEASUREMENT.

WHEN THE FAN SYSTEM IS SHUTDOWN, THE FOLLOWING EVENTS SHALL OCCUR: 1. THE SUPPLY FAN SHALL STOP. 2. THE COOLING COIL CONTROL VALVE SHALL RETURN TO ITS NORMAL POSITION (CLOSED). 3. ITS RESPECTIVE CONTROL SYSTEM SHALL BE DISABLED.

A HAND (OFF) AUTO SWITCH AT THE VFD'S SHALL OVERRIDE THE SYSTEM FOR MAINTENANCE USE.


SUPPLY AIR TEMPERATURE CONTROL: THE SUPPLY AIR TEMPERATURE SENSOR, IN THE AHU DISCHARGE PLENUM, SHALL PROVIDE INPUT TO THE DDC CONTROL SYSTEM. THE SYSTEM SHALL MODULATE THE COOLING COIL 2-WAY CONTROL VALVE AS REQUIRED TO MAINTAIN THE SUPPLY AIR TEMPERATURE AT 68F.

SPACE TEMPERATURE: A TEMPERATURE SENSOR IN THE CLEAN ROOM BAY SHALL PROVIDE INPUT TO THE CONTROL SYSTEM FOR MONITORING PURPOSES.

DUCT SMOKE DETECTOR CONTROL: WHENEVER THE SUPPLY AIR SMOKE DETECTOR IS ACTIVATED, AND A SIGNAL IS SENT TO THE FIRE ALARM PANEL, THE FOLLOWING EVENTS SHALL OCCUR: 1. AN ALARM SHALL BE ANNOUNCED AT THE FIRE ALARM PANEL. NO CONTACTS BY FIRE ALARM CONTRACTOR. CIRCUITRY TO PERFORM CONTROLS BY HVAC CONTRACTOR.

CONTROL POINT LIST - AH-CN-01 THRU AH-CN-08

Table with columns for CONTROL POINT DESCRIPTION, OUTPUT FROM DDC (DIGITAL, ANALOG), INPUT TO DDC (DIGITAL, ANALOG), ALARMS (DIGITAL, ANALOG), and SOFTWARE (APPLICATION PROGRAMS). Rows include AIR HANDLER AH-CN-01 THRU AH-CN-08, SUPPLY FAN VFD, COOLING COIL, SUPPLY AIR FLOW, SUPPLY AIR TEMP, and SPACE TEMPERATURE.



CLEANROOM RECIRCULATION AIR CONTROL DIAGRAM (TYPICAL FOR SYSTEMS AH-CN-01 THRU AH-CN-08)

ORNL DRAWING NUMBER:

Knight/Jacobs Joint Venture 701 Scovboro Road, MS 8253 Oak Ridge, TN 37830 865-241-9433 fax 865-241-3400

M+W Zander U.S. Operations, Inc. 549 West Randolph Street Chicago, IL 60661 Telephone: (312) 877-3200 Fax: (312) 877-3525

UT-BATTELLE Oak Ridge National Laboratory managed for the DEPARTMENT OF ENERGY under U.S. GOVERNMENT contract DE-AC05-00OR22725

PROJECT NAME: CENTER FOR NANOPHASE MATERIALS SCIENCES CLEANROOM RECIRCULATION AIR CONTROL DIAGRAM




Table with columns for RPE, DSN, DRW, CHK, DEPT, PE, PJ, REQ, and DATE. Includes signatures and dates for Bruce W. Johnson and other project members.

Table with columns for REV, DATE, DESCRIPTION, DSN, CHK, DEPT, DATE, PE, DATE, PJ, DATE, REQ, DATE, UTB, DATE, RPE, RPE NO, DATE, ST, CV, EC, EE, EM, IE, M, PD, SE, AR, SQUAD CHECK, and DRAWING APPROVALS.

SECTION AND DETAIL KEY table with columns for NUMBER OF SECTION OR DETAIL and DRAWING ON WHICH SECTION OR DETAIL IS SHOWN OR TAKEN.

THIS DOCUMENT CONTROLLED BY CHANGE CONTROL SYSTEM ENGINEERING PROCEDURE

Table with columns for SH, OF, TYPE, CLASS, REV, and drawing number H8.11.43.