

DESIGN CRITERIA DOCUMENT

WBS 1.4.1

Linac RF System

Date: November 30, 2000



A U.S. Department of Energy Multilaboratory Project

SPALLATION NEUTRON SOURCE

Argonne National Laboratory • Brookhaven National Laboratory • Thomas Jefferson National Accelerator Facility • Lawrence Berkeley National Laboratory • Los Alamos National Laboratory • Oak Ridge National Laboratory

DESIGN CRITERIA DOCUMENT

WBS 1.4.1

Linac RF System

Michael Lynch

Dan Rees

Bill Reass

Amy Regan

**Los Alamos National Laboratory
Spallation Neutron Source**

**Linac RF System
Design Criteria Document**

SNS-2 Group Leader: Michael Lynch
Mike Lynch

SNS-3 Group Leader: Kirk Christensen 1/4/01
Kirk Christensen

Physics Review : James Stovall
Jim Stovall

Project Office Review: Will Fox
Will Fox

Division Director: Don Rej
Don Rej

SNS Linac RF System Design Criteria Document (DCD)

November-30-2000


Outline

-System Description, p 1

-Main Body

1. System Parameters Affecting the Linac RF Design, p 2-4
2. High Power RF Design Parameters, pp 5-18
3. High Voltage Power Conditioning Design Parameters, pp 19-21
4. RF Controls Design Parameters, pp 22-24
5. Interface Control, pp 25-39

System Description



The different structures and frequencies require that 3 different types of klystrons be used. The RFQ and DTL will use 2.5 MW peak klystrons at 402.5 MHz. The CCL will use 5 MW peak klystrons at 805 MHz, and the superconducting cavities will use 550 kW klystrons at 805 MHz. The types and quantities and applications are listed in Table 1.

Table 1: Types and quantities of klystrons and HV systems for the SNS Linac

H Energy	972 MeV
Average beam during pulse	36 mA
Pulse Width	1 ms
Rep Rate	60 Hz
Klystrons	
402.5 MHz, 2.5 MW pk (includes 1 for RFQ, 6 for DTL)	7
805 MHz, 5 MW pk (includes 4 for CCL, 2 for HEBT)	6
805 MHz, 0.55 MW pk, SC	92
HV Converter/Modulators (16 Total)	1 for each 5 MW klystron or pair of 2.5 MW klystrons (except 1 for RFQ and first 2 DTL's & 1 for 2 HEBT cavities) 1 for 11 or 12 0.55 MW klystrons

Main Body

1. System Parameters affecting the Linac RF Design

Pulse Rep Rate	60 Hz
Nominal pulse width	1 ms
Average linac current during pulse	35 mA
Number of RFQ/DTL 402.5 MHz klystrons	7
Number of CCL 5 MW klystrons	4
Number of SC 550 kW klystrons	92
Number of HEBT klystrons	2
Amplitude Control, each system, nominal	$\pm 0.5\%$
Amplitude Control, each system, disable pulse	$\pm 0.75\%$
Phase control, each system, nominal	$\pm 0.5^\circ$
Phase control, each system, disable pulse	$\pm 0.75^\circ$
Excess power margin, minimal design level, 402.5 MHz	25% [power margin = (cavity power + beam power)*1.25]
Excess control power, minimal design level, 805 MHz CCL and SRF	33% [power margin = (cavity power + beam power)*1.33]

The power needed in each cavity when compared to the available klystron power determines the amount of excess power available for controls. The power margin is calculated as the power available above the beam power plus cavity power, divided by the beam power plus cavity power. Table 2 lists the maximum available power margin (if the klystron were set up to provide full rated power) for each cavity and the minimum excess power needed for controls. The SRF cavity powers include the reflective losses which come from using fixed coupling in the medium and high beta cavities. Optimal coupling would require a different coupling setting for each cavity. The numbers do not consider errors in coupling, current level, etc. Those errors are absorbed in the excess power level. The CCL margin is listed at 33% because of the split the CCL waveguide makes and because of the extremely high power level of these klystrons. The excess margin will perhaps allow us to avoid running these klystrons flat-out.

Table 2. Power needed in each cavity, the excess power available, and the minimum excess power needed for controls.

Structure	Structure power (kW)	Beam Power (kW)	Total Power (kW)	Klystron Power (kW)	Maximum Available Power Margin (%)	Minimum margin for RF controls
RFQ	630	130	760	2500	229%	25%
DTL-1	342	178	520	2500	381%	25%
DTL-2	1047	553	1600	2500	56%	25%
DTL-3	1320	610	1930	2500	30%	25%
DTL-4	1326	604	1930	2500	30%	25%
DTL-5	1297	573	1870	2500	34%	25%
DTL-6	1364	516	1880	2500	33%	25%
CCL-1	2127	691	2818	5000	77%	33%
CCL-2	2465	815	3280	5000	52%	33%
CCL-3	2493	887	3380	5000	48%	33%
CCL-4	2530	966	3496	5000	43%	33%

SRF-1	0	165	165	550	234%	33%
SRF-2	0	171	171	550	222%	33%
SRF-3	0	177	177	550	211%	33%
SRF-4	0	183	183	550	201%	33%
SRF-5	0	188	188	550	192%	33%
SRF-6	0	194	194	550	184%	33%
SRF-7	0	199	199	550	177%	33%
SRF-8	0	203	203	550	171%	33%
SRF-9	0	208	208	550	165%	33%
SRF-10	0	211	211	550	160%	33%
SRF-11	0	215	215	550	156%	33%
SRF-12	0	218	218	550	153%	33%
SRF-13	0	220	220	550	150%	33%
SRF-14	0	222	222	550	148%	33%
SRF-15	0	224	224	550	146%	33%
SRF-16	0	225	225	550	145%	33%
SRF-17	0	226	226	550	144%	33%
SRF-18	0	226	226	550	143%	33%
SRF-19	0	226	226	550	143%	33%
SRF-20	0	226	226	550	144%	33%
SRF-21	0	225	225	550	144%	33%
SRF-22	0	224	224	550	145%	33%
SRF-23	0	224	224	550	146%	33%
SRF-24	0	223	223	550	147%	33%
SRF-25	0	221	221	550	148%	33%
SRF-26	0	220	220	550	150%	33%
SRF-27	0	219	219	550	152%	33%
SRF-28	0	217	217	550	154%	33%
SRF-29	0	215	215	550	156%	33%
SRF-30	0	213	213	550	158%	33%
SRF-31	0	211	211	550	160%	33%
SRF-32	0	209	209	550	163%	33%
SRF-33	0	207	207	550	165%	33%
SRF-34	0	239	239	550	130%	33%
SRF-35	0	245	245	550	124%	33%
SRF-36	0	251	251	550	119%	33%
SRF-37	0	257	257	550	114%	33%
SRF-38	0	263	263	550	109%	33%
SRF-39	0	269	269	550	104%	33%
SRF-40	0	275	275	550	100%	33%
SRF-41	0	281	281	550	95%	33%
SRF-42	0	288	288	550	91%	33%
SRF-43	0	294	294	550	87%	33%
SRF-44	0	300	300	550	83%	33%
SRF-45	0	306	306	550	80%	33%
SRF-46	0	312	312	550	76%	33%

SRF-47	0	317	317	550	73%	33%
SRF-48	0	323	323	550	70%	33%
SRF-49	0	329	329	550	67%	33%
SRF-50	0	334	334	550	65%	33%
SRF-51	0	339	339	550	62%	33%
SRF-52	0	344	344	550	60%	33%
SRF-53	0	349	349	550	58%	33%
SRF-54	0	354	354	550	55%	33%
SRF-55	0	358	358	550	53%	33%
SRF-56	0	363	363	550	52%	33%
SRF-57	0	367	367	550	50%	33%
SRF-58	0	371	371	550	48%	33%
SRF-59	0	374	374	550	47%	33%
SRF-60	0	378	378	550	46%	33%
SRF-61	0	381	381	550	44%	33%
SRF-62	0	384	384	550	43%	33%
SRF-63	0	387	387	550	42%	33%
SRF-64	0	390	390	550	41%	33%
SRF-65	0	393	393	550	40%	33%
SRF-66	0	395	395	550	39%	33%
SRF-67	0	397	397	550	38%	33%
SRF-68	0	399	399	550	38%	33%
SRF-69	0	401	401	550	37%	33%
SRF-70	0	403	403	550	37%	33%
SRF-71	0	404	404	550	36%	33%
SRF-72	0	406	406	550	36%	33%
SRF-73	0	407	407	550	35%	33%
SRF-74	0	408	408	550	35%	33%
SRF-75	0	409	409	550	34%	33%
SRF-76	0	410	410	550	34%	33%
SRF-77	0	411	411	550	34%	33%
SRF-78	0	412	412	550	34%	33%
SRF-79	0	412	412	550	33%	33%
SRF-80	0	413	413	550	33%	33%
SRF-81	0	413	413	550	33%	33%
SRF-82	0	413	413	550	33%	33%
SRF-83	0	414	414	550	33%	33%
SRF-84	0	414	414	550	33%	33%
SRF-85	0	414	414	550	33%	33%
SRF-86	0	414	414	550	33%	33%
SRF-87	0	414	414	550	33%	33%
SRF-88	0	414	414	550	33%	33%
SRF-89	0	414	414	550	33%	33%
SRF-90	0	414	414	550	33%	33%
SRF-91	0	414	414	550	33%	33%
SRF-92	0	413	413	550	33%	33%

2. High power RF design parameters

2.1. System Level

402.5 MHz Klystrons per transmitter	1
805 MHz, 5 MW klystrons per transmitter	1
805 MHz, 550 kW klystrons per transmitter	6, max
Circulators	yes, for all klystrons
Splitting of klystron output	only the CCL klystrons (split once)

2.2. Component Parameters, by item

2.2.1. SNS 402.5 MHz, 2.5 MW, Klystrons Specification

RF Operating Frequency	402.5 MHz
Peak Output Power	2.5 MW, minimum
RF Duty Factor	8%
Pulse Repetition Rate	60 Hz
DC to RF Efficiency	58% minimum at rated power.
Beam Voltage	130 kV, Maximum
Beam Current	35 A, Maximum
RF Power Gain	45 dB, Minimum
Instantaneous Bandwidth	± 1.0 MHz 1 dB Minimum Bandwidth at Saturation. ± 0.7 MHz 1 dB Minimum Bandwidth at 80% of saturated output power.

2.2.2. SNS 805 MHz, 5.0 MW, Klystrons Specification

RF Operating Frequency	805.0 MHz
Peak Output Power	5.0 MW, minimum
RF Duty Factor	9%
Pulse Repetition Rate	60 Hz
DC to RF Efficiency	55% minimum at rated power.
Beam Voltage	140 kV, Maximum
Beam Current	88. A, Maximum
RF Power Gain	50 dB, Minimum
Instantaneous Bandwidth	± 1.3 MHz 1 dB Minimum Bandwidth at Saturation. ± 1.0 MHz 1 dB Minimum Bandwidth at 80% of saturated output power.

2.2.3. SNS 805 MHz, 550 kW, Klystrons Specification

RF Operating Frequency	805.0 MHz
Peak Output Power	0.55 MW, minimum
RF Duty Factor	9%
Pulse Repetition Rate	60 Hz
DC to RF Efficiency	65%, minimum at rated power.
Beam Voltage	75 kV, ± 1.5 kV

Beam Current	11.3 A Nominal, 11.5 A Maximum
RF Power Gain	50 dB, Minimum
Instantaneous Bandwidth	± 1.3 MHz 1 dB Minimum Bandwidth at Saturation. ± 1.0 MHz 1 dB Minimum Bandwidth at 80% of saturated output power.

2.2.4. SNS 402.5 MHz, 2.5 MW, Circulator Specification

General

This specification describes the requirements for the 402.5 MHz Y-junction circulator. The circulator shall protect a 2.5 MW peak-power klystron amplifier from reflected power. The pulsed RF will have a maximum pulse repetition frequency of 60 Hz, a maximum duty factor of 8%, and a corresponding maximum pulse width of 1.3 ms.

Performance Specifications

Center Frequency

The center frequency shall be 402.5 MHz.

Forward Power

The maximum forward peak power shall be 2.5 MW with the worst case pulse format described in Section 1.0 above into a fully reflective load at arbitrary phase. Into a load with a maximum VSWR of 2:1 (11% reflected power), the forward power shall be as high as 2.75 MW.

Reverse Power

The maximum reverse peak power at any phase shall be equal to the maximum forward peak power and pulse format.

Insertion Loss

The insertion loss at center frequency at all forward power levels shall be less than 0.07 dB. The insertion loss at the center frequency ± 6 MHz shall be less than 0.17 dB.

Isolation

The isolation at center frequency shall be ≥ 26 dB. The isolation at the center frequency ± 0.5 MHz shall be ≥ 20 dB. The isolation at the center frequency ± 6 MHz shall be ≥ 10 dB.

Return Loss

The input and output VSWR at center frequency shall be less than 1.05:1. The input and output VSWR at center frequency ± 6 MHz shall be less than 1.2:1.

2.2.5. SNS 805 MHz, 5.0 MW, Circulator Specification

General

This specification describes the requirements for an 805 MHz Y-junction circulator. The circulator shall protect a 5.0 MW peak-power klystron amplifier from reflected power. The forward pulsed RF will have a maximum pulse repetition frequency of 60 Hz, a maximum duty factor of 9%, and a corresponding maximum pulse width of 1.5 msec.

Performance Specifications

Center Frequency

The center frequency shall be 805 MHz.

Forward Power

The maximum forward peak power shall be 5.0 MW with the worst case pulse format described in Section 1.0 above into a fully reflective load at arbitrary phase. Into a load with a maximum VSWR of 2:1 (11% reflected power), the forward power shall be as high as 5.5 MW.

Reverse Power

The maximum reverse peak power at any phase shall be equal to the maximum forward peak power of 5.0 MW at a 9% duty.

Insertion Loss

The insertion loss at center frequency at all forward power levels shall be less than 0.07 dB. The insertion loss at the center frequency ± 12 MHz shall be less than 0.17 dB.

Isolation

The isolation at center frequency shall be ≥ 26 dB. The isolation at the center frequency ± 2 MHz shall be ≥ 20 dB. The isolation at the center frequency ± 12 MHz shall be ≥ 10 dB.

Return Loss

The input and output VSWR at center frequency shall be less than 1.05:1. The input and output VSWR at center frequency ± 12 MHz shall be less than 1.2:1.

2.2.6. SNS 805 MHz, 550 kW, Circulator Specification

General

This specification describes the requirements for an 805 MHz Y-junction circulator. The circulator shall protect a 550 kW peak-power klystron amplifier from reflected power. The pulsed RF will have a maximum pulse repetition frequency of 60 Hz, a maximum duty factor of 9%, and a corresponding maximum pulse width of 1.5 ms.

Performance Specifications

Center Frequency

The center frequency shall be 805 MHz.

Forward Power

The maximum forward peak power shall be 550 kW with the worst case pulse format described in Section 1.0 above into a fully reflective load at arbitrary phase. Into a load with a maximum VSWR of 2:1 (11% reflected power), the forward power shall be as high as 610 kW. The forward power shall also be 1.1 MW at a worst case pulse format of 4.5% duty factor, maximum pulse repetition frequency of 60 Hz, and a corresponding maximum pulse width of 0.75 ms into a fully reflective load at arbitrary phase.

Note, this half-duty factor requirement is intended as a testable requirement to insure that the circulator is designed to handle the peak transient fields that have been experienced by accelerators driving super conducting cavities. Analysis and experience has shown that under some circumstances driving a super conducting cavity can result in a short duration transient

standing wave with the peak E and H fields equal to 9 times the nominal traveling wave field when the circulator has ports 2 and 3 terminated in a matched load.

Reverse Power

The maximum reverse peak power at any phase shall be equal to the maximum forward peak power of 550 kW at a 9% duty factor and 1.1 MW at a 4.5% duty factor as described in sections 1.0 and 2.2.

Insertion Loss

The insertion loss at center frequency at all forward power levels shall be less than 0.07 dB. The insertion loss at the center frequency ± 12 MHz shall be less than 0.17 dB.

Isolation

The isolation at the center frequency shall be ≥ 26 dB with ports 2 and 3 of the circulator connected to a high-power load, supplied by the university, with a VSWR of 1.05:1 or better. The isolation at the center frequency ± 2 MHz shall be ≥ 20 dB. The isolation at the center frequency ± 12 MHz shall be ≥ 10 dB.

Return Loss

The input and output VSWR at center frequency shall be less than 1.05:1 with ports 2 and 3 of the circulator connected to a high-power load, supplied by the university, with a VSWR of 1.05:1 or better. The input and output VSWR at center frequency ± 12 MHz shall be less than 1.2:1.

2.2.7. SNS 402.5 MHz, DTL RF Window Specification

This specification is for a RF vacuum window through which power shall be provided to an accelerating cavity by a klystron amplifier.

Center Frequency

The center frequency for the window shall be 402.5 MHz.

Bandwidth

The bandwidth shall be at least 7 MHz centered at 402.5 MHz. All requirements of this specification shall be satisfied over this frequency band except as otherwise noted.

Typical Operation

The typical operating forward power through the window shall be 2.5 MW peak and 200 kW average.

Acceptance Tests (to be performed by Los Alamos National Laboratory)

The high power acceptance tests will be divided into two tests: peak power and average power. The window shall meet all performance and reliability requirements at the following two conditions:

Peak Power

The window shall pass 10 MW peak at 100 μ s pulses, 120 Hz and 120 kW average for 4 hours.

Average power

The windows shall pass 300 kW average power for 4 hours.

2.2.8. SNS 805 MHz, CCL Window Specification

This specification is for a RF vacuum window through which power shall be provided to an accelerating cavity by a klystron amplifier.

Center Frequency

The center frequency for the window shall be 805 MHz.

Bandwidth

The bandwidth shall be at least 14 MHz centered at 805 MHz. All requirements of this specification shall be satisfied over this frequency band except as otherwise noted.

Typical Operation

The typical operating forward power through the window shall be 2.5 MW peak and 200 kW average.

Acceptance Tests (to be performed by Los Alamos National Laboratory)

The high power acceptance tests will be divided into two tests: peak power and average power. The window shall meet all performance and reliability requirements at the following two conditions:

Peak Power

The window shall pass 10 MW peak at 100 μ s pulses, 120 Hz and 120 kW average for 4 hours.

Average power

The windows shall pass 300 kW average power for 4 hours.

2.2.9. SNS 402.5 MHz, 2.5 MW, Load Specification

General

This specification describes the requirements for the 402.5 MHz load. The load shall be used as a test load for a klystron, or as the absorptive load on a circulator. The pulsed RF will have a maximum pulse repetition frequency of 60 Hz, a maximum duty factor of 9%, and a corresponding maximum pulse width of 1.5 ms.

Performance Specifications

All performance specifications shall be met for the full range of inlet and outlet cooling temperatures defined in this specification.

Center Frequency

The center frequency shall be 402.5 MHz.

Forward Power

The maximum peak power that the load shall absorb is 2.5 MW with the worst case pulse format described in Section 1.0 above.

Bandwidth

Except as otherwise noted the load shall meet all requirements of this specification over ± 6 MHz centered at the center frequency.

VSWR

For all conditions described in this specification the VSWR of the load shall be less than 1.07:1 over ± 0.5 MHz centered at the center frequency and less than 1.15:1 over ± 6 MHz centered at the center frequency.

2.2.10. SNS 805 MHz, 5.0 MW, Load Specification**General**

This specification describes the requirements for the 805 MHz load. The load shall be used as a test load for a klystron, as the absorptive load on a circulator, or as the absorptive load on a hybrid splitter. The pulsed RF will have a maximum pulse repetition frequency of 60 Hz, a maximum duty factor of 8%, and a corresponding maximum pulse width of 1.3 ms.

Performance Specifications

All performance specifications shall be met for the full range of inlet and outlet cooling temperatures defined in this specification.

Center Frequency

The center frequency shall be 805 MHz.

Forward Power

The maximum peak power that the load shall absorb is 5.0 MW with the worst case pulse format described in Section 1.0 above with the flow rate of ≈ 80 gpm of water. The load shall meet all performance specifications at 2.0 MW with the worst case pulse format described in Section 1.0 above with the flow rate of ≈ 40 gpm of water.

Bandwidth

Except as otherwise noted the load shall meet all requirements of this specification over ± 12 MHz centered at the center frequency.

VSWR

For all conditions described in this specification the VSWR of the load shall be less than 1.07:1 over ± 1.0 MHz centered at the center frequency and less than 1.15:1 over ± 12 MHz centered at the center frequency.

2.2.11. SNS 805 MHz, 600 kW, Load Specification**General**

This specification describes the requirements for the 805 MHz load. The load shall be used as a test load for a klystron or as the absorptive load on a circulator. The pulsed RF will have a maximum pulse repetition frequency of 60 Hz, a maximum duty factor of 10%, and a corresponding maximum pulse width of 1.6 ms.

Performance Specifications

All performance specifications shall be met for the full range of inlet and outlet cooling temperatures defined in this specification.

Center Frequency

The center frequency shall be 805 MHz.

Forward Power

The maximum peak power that the load shall absorb is 600 kW with the worst case pulse format described in Section 1.0 above with the flow rate of =30 gpm of water.

Bandwidth

Except as otherwise noted the load shall meet all requirements of this specification over ± 12 MHz centered at the center frequency.

VSWR

For all conditions described in this specification the VSWR of the load shall be less than 1.07:1 over ± 1.0 MHz centered at the center frequency and less than 1.15:1 over ± 12 MHz centered at the center frequency.

2.2.12. SNS 402.5 MHz, 2.5 MW, and 805 MHz, 5 MW Transmitter Specification

Introduction

This specification provides the requirements for a transmitter for the Spallation Neutron Source (SNS) accelerator project. The transmitter shall be compatible with one 2.5 MW pulsed klystron amplifier at 402.5 MHz or with one **5 MW** pulsed klystron amplifier at **805 MHz**. Klystron power refers to the klystron's peak RF output power. The klystrons shall be operated with up to an 8% duty factor with variable pulse repetition frequency (prf) which can be varied between **1 and 120 Hz**. The transmitter shall meet all specified requirements at all pulse repetition frequencies between **1 and 120 Hz**. The klystrons are operated with a pulsed cathode voltage. The maximum pulsed voltage and current shall be 135 kV and 40 A, respectively. The maximum peak operating beam power (the product of cathode voltage and current) shall be = 5 MW and the maximum average power shall be = 500 kW.

The **zero to peak value** rise time of the cathode voltage and current pulse will vary between 50 to 150 microseconds. The flat top time of the cathode voltage and current **will be between 0.01 and 1.333 milliseconds when the prf is = 60 Hz. When the prf is between 60 Hz and 120 Hz the flat top time of the cathode voltage and current will be between 0.01 milliseconds and 0.08/prf**. The fall time of the cathode voltage pulse from 100% of the peak voltage to 20% of the peak voltage will vary between **50 and 150 microseconds**. The fall time of the voltage from 20% of peak voltage to zero shall be **150 to 250 microseconds**. All functions required by this specification shall be compatible with this pulse format and over these ranges of rise and fall times. This shall require that many of the measurement and interlock functions described in this specification to be based on sample and hold circuits.

Figure 1 illustrates all the major equipment groups that make up the RF system. This grouping is a functional grouping and is not necessarily representative of the physical configuration of the RF system. The shaded boxes in the figure represent items being purchased under this specification. Those boxes which are not shaded are being furnished separate from this specification by Los Alamos National Laboratory (LANL).




Figure 1. System Block Diagram

2.2.13. SNS 805 MHz, 550 kW Klystron Transmitter Specification

Introduction

This specification provides the requirements for a 805 MHz, 550 kW klystron transmitter for the Spallation Neutron Source (SNS) accelerator project. The transmitter shall support six 550 kW pulsed klystron amplifiers at 805 MHz. Klystron power refers to each klystron's peak RF output power. The klystrons shall nominally be operated at a 9% duty factor at 60 Hz and may be operated with a variable pulse repetition frequency (prf) which can be varied between 1 and 120 Hz. The transmitter shall meet all specified requirements at all pulse repetition frequencies between 1 and 120 Hz. The transmitter shall meet all specified requirements independent of whether the cathode pulses are 60 Hz line synchronized or unsynchronized. The klystrons are operated with a pulsed cathode voltage. The maximum pulsed voltage and current shall be 80 kV and 13 A per klystron or 78 A per transmitter. The maximum peak operating beam power per klystron (the product of cathode voltage and current) shall be = 1 MW and the maximum average beam power per klystron shall be = 90 kW.

The zero to peak value rise time of the cathode voltage and current pulse will vary between 50 to 150 microseconds. The flat top time of the cathode voltage and current will be between 0.01 and 1.5 milliseconds when the prf is = 60 Hz. When the prf is between 60 Hz and 120 Hz the flat top time of the cathode voltage and current will be between 0.01 milliseconds and 0.09/prf. The fall time of the cathode voltage pulse from 100% of the peak voltage to 20% of the peak voltage will vary between 50 and 150 microseconds. The fall time of the voltage from 20% of peak voltage to zero shall be 150 to 250 microseconds. All functions required by this specification shall be compatible with this pulse format and over these ranges of rise and fall times. This shall require that many of the measurement and interlock functions described in this specification to be based on sample and hold circuits.

Figure 2 illustrates all the major equipment groups that make up the RF system. This grouping is a functional grouping and is not necessarily representative of the physical configuration of the RF system. The shaded boxes in the figure represent items being purchased under this specification. Those boxes which are not shaded are being furnished separate from this specification by Los Alamos National Laboratory (LANL).




Figure 2. System Block Diagram

2.3 Waveguide layouts

2.3.1 RFQ waveguide layout

LBNL has primary responsibility for the RFQ waveguide, including the circulator, splitters, and window/coupler assemblies.

2.3.2 DTL waveguide layout

The DTL waveguide layout varies considerably with each module. Two representative layouts are given, one of which does not go through the angled waveguide chase between the klystron gallery and the accelerator (Figure 3), and one which does go through the angled waveguide chase (Figure 4).




Figure 3. DTL layout which does not go through an angled waveguide chase




Figure 4. DTL waveguide which goes through an angled waveguide chase

2.3.3 CCL waveguide layout

The CCL waveguide is the only waveguide system that includes a split. The output of each 5 MW is split into 2 drives to the CCL. Figure 5 shows a representative CCL waveguide run.




Figure 5. CCL waveguide run showing the split and the angled waveguide through the chase.

2.3.4 SRF waveguide layout

The SRF waveguide layout varies from the room temperature waveguide runs in two ways. There are multiple klystrons per transmitter (5 or 6), and the window/coupler assembly is the responsibility of Jefferson Lab.

One transmitter's waveguide configuration is shown in Figure 6. The primary routing of the waveguide from the transmitter to the waveguide chases is shown. Not shown is the waveguide through the chases to the accelerator tunnel.




Figure 6. SRF waveguide layout for one transmitter, showing 6 klystrons

Figure 7 shows one of the SRF waveguide layouts from one transmitter. Each run is relatively simple. The complication comes, as seen in Figure 6, with the density of runs from each transmitter.




Figure 7. One SRF waveguide layout, not including the waveguide run through the chase to the accelerator

3. High Voltage Power Conditioning Design Parameters

3.1. System Parameters. Normal Conducting Linac Klystron Power Requirements


Voltage, peak	140 kV
Current, peak	90 A
Average Power, maximum	1 MW
Peak Power, maximum	11 MW
Rep Rate, max	120 Hz
Pulse width, max (including up to 0.1 ms risetime)	1.25 ms
Number of 402.5 MHz klystrons per supply	2, except first system = 3
Number of 805 MHz klystrons per supply	1, except HEBT system = 2

3.1.1 Detailed Parameters for 140 kV HV system for the normal conducting linac

Rise Time to stable flat top	= 0.1 ms
Output stability for settings from 25 to 100% of full scale	$\pm 0.5\%$
Current range, peak	5 to 90 A
Input voltage	13.8 kV AC RMS $\pm 3\%$, 3 phase, 60 Hz
Efficiency for voltages between 85% and 100% of the maximum rated voltage and 75% and 100% of the maximum rated current	= 85%

The major sub unit of the HVPPS located within the klystron gallery shall deposit no more than 30 kW of heat into the air of the klystron gallery under all operating conditions.

Absolute maximum values for the frequency components of the output voltage ripple during the stable flat top portion of the output pulse for frequencies between 750 Hz and 30 kHz:



3.2. System Parameters. Superconducting Linac Klystron Power Requirements


Voltage, peak	80 kV
Current, peak	140 A
Average Power, maximum	1 MW
Peak Power, maximum	11 MW
Rep Rate, max	120 Hz
Pulse width, max (including up to 0.1 ms risetime)	1.4 ms
Number of klystrons per supply	11 or 12

3.2.1 Detailed Parameters for 80 kV HV system for the superconducting linac

Rise Time to stable flat top	= 0.1 ms
Output stability for settings from 50 to 100% of full scale	±0.5%
Current range, peak	2 to 140 A
Input voltage	13.8 kVAC ±3%, 3 phase, 60 Hz
Efficiency for voltages between 85% and 100% of the maximum rated voltage and 75% and 100% of the maximum rated current	= 85%

The major sub unit of the HVPPS located within the klystron gallery shall deposit no more than 30 kW of heat into the air of the klystron gallery under all operating conditions.

Absolute maximum values for the frequency components of the output voltage ripple during the stable flat top portion of the output pulse for frequencies between 750 Hz and 30 kHz:



4. RF Controls Design Parameters

4.1. System Level Parameters


Parameter	Value
Pulse Rep Rate	60.0 Hz (and, possibly, 10.00 Hz interleaved)
MacroPulse Width	0.945 ns (645 ns ON/300 ns OFF), 1.1886 MHz
LINAC Length	Approximately 335 m
RFQ Resonance Control Requirement	F_0 : 402.5 MHz \pm 15 kHz Q_L = 3,300 BW = 122 kHz
DTL Resonance Control Requirement	F_0 : 402.5 MHz \pm 2 kHz Q_L : 25,000 (smallest bandwidth case) BW = 16 kHz
CCL Resonance Control Requirement	F_0 : 805 MHz \pm 10 kHz Q_L : 10,000 (smallest bandwidth case) BW = 80 kHz
SRF $\beta=0.61$ Resonance Control Requirement	F_0 : 805 MHz \pm 500 Hz Q_L : 733,000 \pm 20% BW = 1 kHz
SRF $\beta=0.61$ Lorentz constant	2.9 Hz/(MV/m) ²
SRF $\beta=0.81$ Resonance Control Requirement	F_0 : 805 MHz \pm 500 Hz Q_L : 699,000 \pm 20% BW = 1 kHz
SRF $\beta=0.81$ Lorentz constant	1.2 Hz/(MV/m) ²
Field Control Requirement, all cavities	<u>Amplitude Tolerance</u> : \pm 0.5% Max in steady state, \pm 0.75% during beam turn-on transient. <u>Phase Tolerance</u> : \pm 0.5° Max in steady state, \pm 0.75° during beam turn-on transient.

4.2 Detailed design parameters


RF Control System (RFCS) Functions

The four primary functions of the RFCS are control of the cavity fields (Field Control), detection and control of the cavity resonance (Resonance Control), protection of the klystrons and cavities from high power faults (High Power Protection) and the radio frequency reference distribution subsystem. See Figure below.

System Functional Block Diagram



The selected architecture for the RF Control System is VXIbus. Each of these global functions, with the exception of the Reference Generation and Distribution, will be located on a VXIbus module. In broad terms, the Field, Resonance, and Amplifier Control functions are performed by a Field / Resonance Control Module (FRCM) in conjunction with a Clock Distribution Module (CDM); and the High Power Protect function is performed by a HPRF Protect Module (HPM). The figure below shows one example (CCL) of how these functions are interconnected in the various stages of the LINAC.



A description of the modules is given below:

Field / Resonance Control Module (FRCM)

The FRCM continuously monitors both the cavity field amplitude and phase and the actual cavity resonance frequency. The field control portion of the module minimizes deviations of the cavity field amplitude and phase from their respective setpoints. The resonance control portion of the module, depending on the magnitude of the error between the actual resonance frequency and the desired operating frequency, takes actions to move the cavity resonance to the operating frequency, either by slewing the drive frequency, issuing a correction signal to the Resonant Cavity Control System (RCCS), or both.

High Power Protection Module (HPM)

The High Power Protection Module (HPM) continuously monitors the high power RF distribution system using RF power detectors, fiber optic arc detectors, and the vacuum permit system. It can shut off the RF carrier and/or the injector in the event of faults.

Clock Distribution Module (CDM)

The Clock Distribution Module (CDM) generates the master timing signals for the other LANL modules in the VXibus crate. It also receives timing information from the Brookhaven National Laboratory's (BNL) Event Link Module and reformats it for the LBUS (Local Bus) on the crate backplane for use by the various modules.

Frequency Reference System (REF)

The key to operating the accelerator RF control system is a stable frequency reference distributed to the various control racks. The reference system is designed to maintain a total phase error in the reference frequencies of $\pm 0.1^\circ$ over the entire length of the accelerator. To minimize the error contribution of the frequency reference system, the reference signals are distributed in insulated, temperature-controlled coaxial lines.

Reference Line specifications


Parameter	Specification
Frequency:	755 MHz or 352.5 MHz (depending on location)
Length:	335 m
Phase Stability:	$\pm 0.1^\circ$ @ 755 MHz
Taps	
Number of Taps:	95
Tap Power:	+21 dBm
Tap Coupling:	> 20 dB, variable in 1 dB steps
Amplifier Power:	50 Watts (+47 dBm)
Main Line	
Line Type:	3 1/8" rigid copper co-ax; pressurized with dry air
Line Lengths:	20 ft. sections with slip joints every 100 ft.
Temperature Control Method:	Electric heater and controller every 100 ft.
Temperature Control Stability:	$\pm 0.1^\circ$ C (40° C nominal temperature)
Pressure Control:	+/- 1 torr
IF Distribution Line	
Line Type:	3/8" Heliax for LO distribution to Clock Module
Line Lengths:	100 ft. insulated and temperature controlled to $\pm 0.1^\circ$ C @ 40° C

5. Interface Control


The majority of the interfaces for the RF system are through the RF control system. Some brief interfaces are shown below for the High Power RF and HV systems. The majority of their interfaces are contained in the detailed specifications of the hardware.

5.1. High Power RF Interfaces


DTL RF Power Water system layout:



CCL RF Power Water System Layout:



SRF RF Power Water System Layout:



5.2. HV Power Conditioning Interfaces, 80 kV and 140 kV systems

AC Power Source for HVPPS

Input Voltage

The input voltage shall be 13.8 kV AC RMS $\pm 3\%$, 3 phase, 60 Hz.

Unbalance

Under normal conditions, the voltage unbalance from phase to phase in the power provided by ORNL shall be = 3.8%.

Harmonic Distortion

The input current harmonics generated at the 13.8 kV input by an individual HVPPS system and by the set of all HVPPS systems under all operational scenarios defined in this specification shall conform to the recommended practices defined in IEEE Std 519-1992.

Power Factor

The displacement component of the power factor that HVPPS presents to the source shall be = 0.93 when operating at voltages between 85% and 100% of the maximum rated voltage and 75% and 100% of the maximum rated current.

Physical Layout


The HVPPS shall fit within the areas described below. The HVPPS system shall be divided into three separate major sub units and a small remote sub unit. The floor loading of each sub unit shall be = 500 pounds per square foot. The location and maximum area allowed for each sub unit is as follows.

Sub Unit #1

A local control rack will be located within the klystron gallery. The local control rack shall be a standard 19 inch rack that is = 8 feet high. The maximum distance from the control rack to sub unit #2 shall be = 100 feet.

Sub Unit #2

This sub unit shall occupy no more than an "L" shaped floor space that is 13 feet by 15 feet in the longest dimensions as shown in figure below. All parts of sub unit #2 shall fit within the "L" shaped footprint envelope shown in figure. The "L" shaped footprint envelope shall have a perimeter whose sides are 15 feet, 13 feet, 10 feet, 8 feet, 5 feet and 5 feet; as shown in figure 3. The height of this sub unit shall be = 10 feet.



The HVPPS sub unit #2 footprint envelope.


This sub unit shall be capable of being disassembled into moveable components without the use of an overhead crane. All components of this sub unit shall be capable of being transported by fork lift down a aisle with a width of 7 feet and a height of 15 feet.

Sub Unit #3

The exterior sub unit shall comply with the 1993 National Electrical Code and shall be NEMA 3R or greater. The maximum size of this sub unit shall be 8.5 feet by 13.5 feet. The floor loading of this sub unit on the slab shall be = 500 pounds per square foot. Insulating oil will not be used in the exterior sub unit.

ORNL will provide a weatherized switchgear cabinet adjacent to one of the short sides of the sub unit. The placement of the ORNL switchgear will prevent any access to this side of the sub unit. Access to this side of the sub unit shall not be required for servicing or maintenance after the sub unit is installed. A 6 inch diameter conduit provided by ORNL shall connect the sub unit to the switchgear. The sub unit shall be compatible with an input connection of this type. In addition, the sub unit shall also be compatible with an input connection to a 6 inch diameter underground conduit entering the underside of the unit. The sub unit shall be compatible with all input conduit connections from below that fall within the shaded area for input connections as shown in figure below. These locations are shown as viewed from ABOVE the sub unit.

A 6 inch diameter underground conduit with a minimum bend radius of 2 feet shall be provided by ORNL and shall be available to connect any high voltage connections between the exterior HVPPS sub unit and interior sub unit #2. In addition, a 2 inch diameter underground conduit shall be provided by ORNL to provide cooling and control power and connect control and fiber optic lines between the exterior HVPPS sub unit and any and all interior sub units. Both conduits will stub up through the concrete pad. These conduits shall stub up **BELOW THE EXTERIOR SUB UNIT** near the end opposite from the switchgear.



The sub unit shall be compatible with 6" conduit connections that fall within the shaded areas.

All cable and busway termination compartments and terminations shall comply with the 1999 National Electrical Code and shall be NEMA 3R or greater for all equipment located outside the facility. The length of these conduits is different for each HVPPS system but shall be between 75 feet and 300 feet.

Remote Sub Unit

A remote sub unit indicates the "real time" output voltage and current. ORNL shall mount the remote sub unit to a standard "DIN rail" located near the back of a standard 19 inch rack. The maximum dimensions of the remote sub unit shall be such that the remote sub unit can fit within a cube that is 6 inches on each side. The remote sub unit shall not be visible from the front of the rack under normal operation.

5.3. RF Controls Interfaces

5.3.1. RFCS RFQ Interface

RFQ External Inputs/Outputs

RFCS Subsystem	RFCS Signal	Description
CDM	T ₀ In	T ₀ signal from Timing Module to CDM - TBD
CDM	352.5 LO In	LO Signal from Reference system in tunnel. 352.5 MHz/+10 dBm
CDM	2.5 MHz In	2.5 MHz / +10 dBm from Reference Rack
FRCM	Diagnostic In	Beam feed forward input from Diagnostic Group Rack – TBD
FRCM	FO I/Q Out	Pair of Digital FO data links to Control Room patch panel – TBD
FRCM	RCCS Out	±5V error signal to RFCS RCCS Differential amp box located at RCCS rack. Output of Differential amp is 0-10V to RCCS.
FRCM	CAV Field IF In	50 MHz/+0 dBm cavity field reference
FRCM	CAV FWD RF In	Forward power into splitter – 402.5 MHz/+10 dBm max
FRCM	CAV RFL RF In	Reflected power from splitter – 402.5 MHz/+10 dBm max
FRCM	RF Out	402.5 MHz feed to transmitter
HPM	RF_PERMIT In	Input from MPS or Vacuum System – Opto-isolated Rx at HPM. HIGH = OK
HPM	RF_FAULT* Out	Output to MPS – Opto-isolated Rx at MPS. HIGH = OK
HPM	RF 0 In	Cavity Field Probe – 402.5 Mhz/+10 dBm Max
HPM	RF 1 In	Klystron-Circulator Forward Power – 402.5 Mhz/+10 dBm Max
HPM	RF 2 In	Klystron-Circulator Reflected Power – 402.5 Mhz/+10 dBm Max
HPM	RF 3 In	Circulator-Splitter Forward Power – 402.5 Mhz/+10 dBm Max
HPM	RF 4 In	Circulator-Splitter Reflected Power– 402.5 Mhz/+10 dBm Max
HPM	RF 5 In	16:1 Multiplexer output – 402.5 Mhz/+10 dBm Max 8 cavity field probes – Channel assignments TBD 8 window forward power - Channel assignments TBD
HPM	RF 6 In	16:1 Multiplexer output – 402.5 Mhz/+10 dBm Max 8 cavity field probes - Channel assignments TBD 8 window reflected power - Channel assignments TBD
HPM	BB 7 In	Not used
HPM	FOARC 00 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD

RFCS Subsystem	RFCS Signal	Description
HPM	FOARC 01 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 02 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 03 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 04 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 05 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 06 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 07 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 08 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 09 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 10 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 11 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 12 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 13 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
REF	TC 1 In	Input from Thermocouple 1 in the reference line in the tunnel.
REF	TC 2 In	Input from Thermocouple 2 in the reference line in the tunnel.
REF	CNTL 1 Out	115VAC out to heater strip 1 in the reference line in the tunnel.
REF	CNTL 2 Out	115VAC out to heater strip 2 in the reference line in the tunnel.
REF	RS-485 COM	Bi-directional RS-485 communications between REF heater controller and EPICS.

RFQ Cable Lists

Signal Description – RFCS RFQ Subsystem	Signal Type	Connection Medium	Location	>1?
Cavity field to mixer RF port	RF	Heliac	Tunnel	
Tunnel reference line to mixer LO port	RF-50MHz	Heliac	Tunnel	
Cavity field IF from mixer to RFCS (FRCM)	50 MHz	Heliac	Tunnel to gallery	
Cavity field pickup loops for instrumentation (>4 requires a mux) n=16 (will be mux'd to two)	RF	Heliac	Tunnel to gallery	yes
Pickup loop for cavity arc detection (HPPS) Cavity to RFCS	RF	Heliac	Tunnel to gallery	
D/C on W/G feed back to RFCS (HPPS) (for cavity arc detection)	RF	Heliac	Tunnel to gallery	
D/C on circulator load (to HPPS)	RF	Heliac	gallery	
D/C at 1 of 8 feeds to cavity (n=8) will go to 16:1 mux for monitoring fwd/refl at cavity	RF	Heliac	Tunnel to gallery	yes
D/C at 1 of 8 feeds to cavity (HPPS). n=8. will go to 16:1 mux for monitoring fwd/refl at cavity	RF	Heliac	Tunnel to gallery	
Upstream of 8-way split. Back to HPPS	RF	Heliac	Gallery only ?	
Upstream of 8-way split. Back to HPPS	RF	Heliac	Gallery only ?	
Output to “Beam Off” Fast Protect system	TTL	TBD	Gallery	
Input from Machine Protect System– “OK for RF on”	TTL	TBD	Gallery	
Fiber optic arc detector signal from HPRF rack (where arc detectors are located).	TTL	TBD	Gallery	yes

Signal Description – RFCS RFQ Subsystem	Signal Type	Connection Medium	Location	>1?
Contains info about arc in waveguide. n=14				

5.3.2. RFCS DTL and HEBT

DTL and HEBT External Inputs/Outputs

RFCS Subsystem	RFCS Signal	Description
CDM	T ₀ In	T ₀ signal from Timing Module to CDM - TBD
CDM	352.5 LO In	LO Signal from Reference system in tunnel. 352.5 MHz/+10 dBm
CDM	2.5 MHz In	2.5 MHz / +10 dBm from Reference Rack
FRCM	Diagnostic In	Beam feed forward input from Diagnostic Group Rack – TBD
FRCM	FO I/Q Out	Pair of Digital FO data links to Control Room patch panel – TBD
FRCM	RCCS Out	±5V error signal to RFCS RCCS Differential amp box located at RCCS rack. Output of Differential amp is 0-10V to RCCS.
FRCM	CAV Field IF In	50 MHz/+0 dBm cavity field reference
FRCM	CAV FWD RF In	Forward power into splitter – 402.5 MHz/+10 dBm max
FRCM	CAV RFL RF In	Reflected power from splitter – 402.5 MHz/+10 dBm max
FRCM	RF Out	402.5 MHz feed to transmitter
HPM	RF_PERMIT In	Input from MPS or Vacuum System – Opto-isolated Rx at HPM. HIGH = OK
HPM	RF_FAULT* Out	Output to MPS – Opto-isolated Rx at MPS. HIGH = OK
HPM	RF 0 In	Cavity Field Probe – 402.5 Mhz/+10 dBm Max
HPM	RF 1 In	Circulator Load Forward Power – 402.5 Mhz/+10 dBm Max
HPM	RF 2 In	Circulator – Cavity Reflected Power – 402.5 Mhz/+10 dBm Max
HPM	RF 3 In	Instrumentation Channel 1 – 402.5 Mhz/+10 dBm Max
HPM	RF 4 In	Spare
HPM	RF 5 In	Spare
HPM	RF 6 In	Spare
HPM	BB 7 In	Phase detector Input - ± 100 mV baseband
HPM	FOARC 00 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 01 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 02 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 03 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 04 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 05 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 06 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 07 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
REF	TC 1 In	Input from Thermocouple 1 in the reference line in the tunnel.
REF	TC 2 In	Input from Thermocouple 2 in the reference line in the tunnel.
REF	CNTL 1 Out	115VAC out to heater strip 1 in the reference line in the tunnel.
REF	CNTL 2 Out	115VAC out to heater strip 2 in the reference line in the tunnel.

RFCS Subsystem	RFCS Signal	Description
REF	RS-485 COM	Bi-directional RS-485 communications between REF heater controller and EPICS.

RFCS DTL Cables

Signal Description – RFCS DTL Subsystem	Signal Type	Connecti on Medium	Location	>1?
Cavity field to mixer RF port	RF	Heliax	Tunnel	
Tunnel reference line to mixer LO port	RF-50MHz	Heliax	Tunnel	
Cavity field IF from mixer to RFCS (FRCM)	50 MHz	Heliax	Tunnel to Gallery	
Cavity field pickup loops for instrumentation	RF	Heliax	Tunnel to Gallery	No. only 1
Pickup loop for cavity arc detection (HPPS) Cavity to RFCS	RF	heliax	Tunnel to Gallery	
D/C on W/G feed back to RFCS (HPPS) (for cavity arc detection)	RF	Heliax	Tunnel to Gallery	
D/C on circulator load (to HPPS)	RF	Heliax	Gallery	
Pickup-loop from upstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Pickup-loop from downstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Signal from mixer used as a phase detector. Mixer to HPPS	Quasi-DC	Coax (Times LMR 100?)		
Output to “Beam Off” Fast Protect system	TTL	TBD	Gallery	
Input from cavity vacuum – “OK for RF on”	TTL	TBD	Gallery	
Fiber optic arc detector signal from HPRF rack (where arc detectors are located). Contains info about arc in waveguide. n=8	TTL	TBD	Gallery	yes

RFCS HEBT Cables

Signal Description – RFCS HEBT Subsystem	Signal Type	Connecti on Medium	Location	>1?
Cavity field to mixer RF port	RF	Heliax	Tunnel	
Tunnel reference line to mixer LO port	RF-50MHz	Heliax	Tunnel	
Cavity field IF from mixer to RFCS (FRCM)	50 MHz	Heliax	Tunnel to Gallery	
Cavity field pickup loops for instrumentation	RF	Heliax	Tunnel to Gallery	Yes 2
Pickup loop for cavity arc detection	RF	Heliax	Tunnel to Gallery	

Signal Description – RFCS HEBT Subsystem	Signal Type	Connecti on Medium	Location	>1?
(HPPS) Cavity to RFCS				
D/C on W/G feed back to RFCS (HPPS) (for cavity arc detection)	RF	Heli ax	Tunnel to Gallery	
D/C on circulator load (to HPPS)	RF	Heli ax	Gallery	
D/C on circulator load (to HPPS)	RF	Heli ax	Gallery	
Pickup-loop from upstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Pickup-loop from downstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Signal from mixer used as a phase detector. Mixer to HPPS	Quasi-DC	Coax (Times LMR 100?)		
Output to “Beam Off” Fast Protect system	TTL	TBD	Gallery	
Input from Machine Protect System – “OK for RF on”	TTL	TBD	Gallery	
Fiber optic arc detector signal from HPRF rack (where arc detectors are located). Contains info about arc in waveguide. n=8	TTL	TBD	Gallery	yes

5.3.3. RFCS CCL

CCL External Inputs/Outputs

RFCS Subsystem	RFCS Signal	Description
CDM	T ₀ In	T ₀ signal from Timing Module to CDM - TBD
CDM	755 LO In	LO Signal from Reference system in tunnel -- 755.0 MHz/+10 dBm
CDM	2.5 MHz In	2.5 MHz / +10 dBm from Reference Rack
FRCM	Diagnostic In	Beam feed forward input from Diagnostic Group Rack – TBD
FRCM	FO I/Q Out	Pair of Digital FO data links to Control Room patch panel – TBD
FRCM	RCCS Out	±5V error signal to RFCS RCCS Differential amp box located at RCCS rack. Output of Differential amp is 0-10V to RCCS.
FRCM	CAV Field IF In	50 MHz/+0 dBm cavity field reference
FRCM	CAV FWD RF In	Forward power into splitter – 805.0 MHz/+10 dBm max
FRCM	CAV RFL RF In	Reflected power from splitter – 805.0 MHz/+10 dBm max
FRCM	RF Out	805.0 MHz feed to transmitter

RFCS Subsystem	RFCS Signal	Description
HPM	RF_PERMIT In	Input from MPS or Vacuum System – Opto-isolated Rx at HPM. HIGH = OK
HPM	RF_FAULT* Out	Output to MPS – Opto-isolated Rx at MPS. HIGH = OK
HPM	RF 0 In	Cavity Field Probe – 805.0 MHz/+10 dBm max
HPM	RF 1 In	Circulator Load Forward Power – 805.0 MHz/+10 dBm max
HPM	RF 2 In	Splitter Load Forward Power – 805.0 MHz/+10 dBm max
HPM	RF 3 In	Cavity Feed Reflected Power 1 – 805.0 MHz/+10 dBm max
HPM	RF 4 In	Cavity Feed Reflected Power 2 – 805.0 MHz/+10 dBm max
HPM	RF 5 In	Instrumentation Channel 1 – 805.0 MHz/+10 dBm max
HPM	RF 6 In	Instrumentation Channel 2 – 805.0 MHz/+10 dBm max
HPM	BB 7 In	Phase detector Input - ± 100 mV baseband
HPM	FOARC 00 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 01 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 02 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 03 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 04 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 05 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 06 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 07 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 08 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 09 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 10 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
REF	TC 1 In	Input from Thermocouple 1 in the reference line in the tunnel.
REF	TC 2 In	Input from Thermocouple 2 in the reference line in the tunnel.
REF	CNTL 1 Out	115VAC out to heater strip 1 in the reference line in the tunnel.
REF	CNTL 2 Out	115VAC out to heater strip 2 in the reference line in the tunnel.
REF	RS-485 COM	Bi-directional RS-485 communications between REF heater controller and EPICS.

RFCS CCL Cables

Signal Description – RFCS CCL Subsystem	Signal Type	Connection Medium	Location	>1?
Cavity field to mixer RF port	RF	Heliac	Tunnel	
Tunnel reference line to mixer LO port	RF-50MHz	Heliac	Tunnel	
Cavity field IF from mixer to RFCS (FRCM)	50 MHz	Heliac	Tunnel to Gallery	
Cavity field pickup loops for instrumentation	RF	Heliac	Tunnel to Gallery	Yes 2
Pickup loop for cavity arc detection (HPPS) Cavity to RFCS	RF	Heliac	Tunnel to Gallery	
D/C on W/G feed back to RFCS (HPPS) (for cavity arc detection)	RF	Heliac	Tunnel to Gallery	
D/C on circulator load (to HPPS)	RF	Heliac	Gallery	
D/C on circulator load (to HPPS)	RF	Heliac	Gallery	
Pickup-loop from upstream cavity to mixer for cavity to cavity phase	RF	Coax (Times		

Signal Description – RFCS CCL Subsystem	Signal Type	Connecti on Medium	Location	>1?
detection		LMR 100?)		
Pickup-loop from downstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Signal from mixer used as a phase detector. Mixer to HPPS	Quasi-DC	Coax (Times LMR 100?)		
Output to “Beam Off” Fast Protect system	TTL	TBD	Gallery	
Input from Machine Protect System – “OK for RF on”	TTL	TBD	Gallery	
Fiber optic arc detector signal from HPRF rack (where arc detectors are located). Contains info about arc in waveguide. n=11	TTL	TBD	Gallery	yes

5.3.4. RFCS SRF

SRF External Inputs/Outputs

RFCS Subsystem	RFCS Signal	Description
CDM	T ₀ In	T ₀ signal from Timing Module to CDM - TBD
CDM	755 LO In	LO Signal from Reference system in tunnel -- 755.0 MHz/+10 dBm
CDM	2.5 MHz In	2.5 MHz / +10 dBm from Reference Rack
FRCM	Diagnostic In	Beam feed forward input from Diagnostic Group Rack – TBD
FRCM	FO I/Q Out	Pair of Digital FO data links to Control Room patch panel – TBD
FRCM	RCCS Out	±5V error signal to RFCS RCCS Differential amp box located at RCCS rack. Output of Differential amp is 0-10V to RCCS.
FRCM	CAV Field IF In	50 MHz/+0 dBm cavity field reference
FRCM	CAV FWD RF In	Forward power into cavity – 805.0 MHz/+10 dBm max
FRCM	CAV RFL RF In	Reflected power from cavity – 805.0 MHz/+10 dBm max
FRCM	RF Out	805.0 MHz feed to transmitter
HPM	RF_PERMIT In	Input from MPS or Vacuum System – Opto-isolated Rx at HPM. HIGH = OK
HPM	RF_FAULT* Out	Output to MPS – Opto-isolated Rx at MPS. HIGH = OK
HPM	RF 0 In	Cavity Field Probe – 805.0 MHz/+10 dBm max
HPM	RF 1 In	Circulator Load Forward Power – 805 MHz/+10 dBm max
HPM	RF 2 In	Circulator – Cavity Reflected Power – 805.0 MHz/+10 dBm max
HPM	RF 3 In	Spare

RFCS Subsystem	RFCS Signal	Description
HPM	RF 4 In	Spare
HPM	RF 5 In	Spare
HPM	RF 6 In	Spare
HPM	BB 7 In	Phase detector Input - ± 100 mV baseband
HPM	FOARC 00 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 01 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 02 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
HPM	FOARC 03 In	Input from HPRF System – Opto-isolated Rx at HPM – Connector TBD
REF	TC 1 In	Input from Thermocouple 1 in the reference line in the tunnel.
REF	TC 2 In	Input from Thermocouple 2 in the reference line in the tunnel.
REF	CNTL 1 Out	115VAC out to heater strip 1 in the reference line in the tunnel.
REF	CNTL 2 Out	115VAC out to heater strip 2 in the reference line in the tunnel.
REF	RS-485 COM	Bi-directional RS-485 communications between REF heater controller and EPICS.

RFCS SRF Cables

Signal Description – RFCS SRF Subsystem	Signal Type	Connection Medium	Location	>1?
Cavity field to mixer RF port	RF	Heliac	Tunnel	
Tunnel reference line to mixer LO port	RF-50MHz	Heliac	Tunnel	
Cavity field IF from mixer to RFCS (FRCM)	50 MHz	Heliac	Tunnel to Gallery	
Cavity field pickup loops for instrumentation	RF	Heliac	Tunnel to Gallery	Yes 2
Pickup loop for cavity arc detection (HPPS) Cavity to RFCS	RF	Heliac	Tunnel to Gallery	
D/C on W/G feed back to RFCS (HPPS) (for cavity arc detection)	RF	Heliac	Tunnel to Gallery	
D/C on circulator load (to HPPS)	RF	Heliac	Gallery	
D/C on circulator load (to HPPS)	RF	Heliac	Gallery	
Pickup-loop from upstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Pickup-loop from downstream cavity to mixer for cavity to cavity phase detection	RF	Coax (Times LMR 100?)		
Signal from mixer used as a phase detector. Mixer to HPPS	Quasi-DC	Coax (Times LMR 100?)		
Output to “Beam Off” Fast Protect system	TTL	TBD	Gallery	
Input from Machine Protect System – “OK for RF on”	TTL	TBD	Gallery	
Fiber optic arc detector signal from	TTL	TBD	Gallery	yes

Signal Description – RFCS SRF Subsystem	Signal Type	Connection Medium	Location	>1?
HPRF rack (where arc detectors are located). Contains info about arc in waveguide. n=5				

5.3.5. Vxibus Backplane Definition

Channel	Name	Source	User	Function
ECLTRG00	40MHZ	CDM	ALL	40 MHZ clock (falling edge mark)
ECLTRG01	10MHZ	CDM	ALL	10 MHZ clock (falling edge mark sync'd to 40 MHz)
LBUS[00..11]	LBUS			Event Link Data - TBD
TTLTRG0*	SAMPLE*	CDM	ALL	Synchronous data sample strobe. Latch data on falling edge, clear data registers on rising edge.
TTLTRG1*				Spare
TTLTRG2*				Spare
TTLTRG3*	RF_GATE*	CDM	ALL	LOW when RF is ON / HIGH when OFF. [See Note]
TTLTRG4*	T ₀	CDM	ALL	T ₀ sync pulse from master timing system. Falling edge is fiducial. [See Note]
TTLTRG5*	FAULT_L*	ALL	HPM	RF fault in LEFT half of crate. (Klystron A). LOW = FAULT (RF off)
TTLTRG6*	RF_FAULT*	HPM	MPS FRCM	Tell MPS to turn off beam during faults. LOW = FAULT (Beam off)
TTLTRG7*	FAULT_R*	ALL	HPM	RF fault in RIGHT half of crate. (Klystron B). LOW = FAULT (RF off)

Table Notes:

1. The HPM has one input (RF_PERMIT) and one output (RF_FAULT*) to the machine protection system (MPS). If RF_PERMIT goes low, the HPM pulls TTLTRG5*, TTLTRG6* and TTLTRG7* low on the backplane. Likewise, if either TTLTRG5* or TTLTRG6* are asserted on the backplane, the HPM pulls RF_FAULT* output low to notify MPS of the fault.
2. Timing between TTLTRG3* and TTLTRG4* is **TBD**.